

Westview Projects

Hilan Village



Transportation Impact Assessment



Hilan Village

Transportation Impact Assessment

Prepared for:

Westview Projects
c/o Seth Richards
18 Louisa Street, Suite 180
Ottawa, ON K1R 6Y6

Prepared by:



6 Plaza Court
Nepean, ON K2H 7W1

April 2022

PN: 2021-133

Table of Contents

1	Introduction.....	1
1.1	Existing Conditions	3
1.1.1	Area Road Network	3
1.1.2	Existing Intersections.....	4
1.1.3	Existing Driveways	5
1.1.4	Cycling and Pedestrian Facilities.....	5
1.1.5	Existing Transit.....	7
1.1.6	Existing Peak Hour Travel Demand.....	7
2	Future Background Conditions.....	9
2.1	Planned Conditions.....	9
2.1.1	Changes to the Area Transportation Network	9
2.1.2	Other Study Area Developments.....	9
2.1.3	Background Growth.....	9
2.1.4	Future Background Traffic Volumes	9
3	Demand Forecasting.....	10
3.1	Site Trip Generation	10
3.2	Vehicle Traffic Distribution and Assignment	11
3.3	Future Total Travel Demands	12
4	Operational Analysis.....	13
4.1	2022 Existing Operational Analysis.....	14
4.2	Future Background Conditions	15
4.2.1	Future Background Traffic Control Warrants	15
4.2.2	Future Background Intersection Design	15
4.2.3	Future Background 2028 Conditions	15
4.3	Future Total Conditions.....	15
4.3.1	Future Total Traffic Control Warrants	15
4.3.2	Future Total Intersection Design	16
4.3.3	Future Total 2028 Conditions	16
5	Site Plan Review	17
5.1	Site Circulation.....	17
5.2	Site Access	17
5.3	Parking Supply	17
5.4	Active Mode Considerations	17
6	Findings and Recommendations	17

List of Figures

Figure 1:	Area Context Plan	1
Figure 2:	Draft Plan of Subdivision	2
Figure 3:	Ottawa Valley Rail Trail - Looking North at Carss Street	6
Figure 4:	Ottawa Valley Rail Trail - Looking South at Carss Street	6
Figure 5:	2022 Existing Traffic Volumes	8

Figure 6: 2028 Future Background Traffic Volumes 10
Figure 7: New Site-Generated Traffic Volumes 12
Figure 8: 2028 Future Total Traffic 13

Table of Tables

Table 1: Turning Movement Count Data Dates 7
Table 2: Ottawa Valley Rail Trail Crossing Volume Counts 8
Table 3: ITE Trip Generation Rate 11
Table 4: Vehicle Site Trip Generation 11
Table 5: Peak Hour Factors 14
Table 6: Level of Service Criteria for Unsignalized Intersections 14
Table 7: 2022 Existing Intersections Operational Analysis 14
Table 8: 2028 Future Background Conditions Operational Analysis 15
Table 9: 2028 Future Total Conditions Operational Analysis 16

List of Appendices

- Appendix A – Terms of Reference (TOR)
- Appendix B – Adjustment Factor
- Appendix C – Traffic Data
- Appendix D – Heavy Vehicle Percentage Calculations
- Appendix E – 2022 Existing Synchro Worksheets
- Appendix F – Signal Warrants
- Appendix G – Left-turn Lane Warrants
- Appendix H – 2028 Future Background Synchro Worksheets
- Appendix I – 2028 Future Total Synchro Worksheets

1 Introduction

This Transportation Impact Assessment has been prepared to support the proposed development of Hilan Village in the Ward of Almonte. The subject site is located at the northwest corner of Carss Street and the Ottawa Valley Rail Trail and is currently designated as a Development (D2) Zone. The site is proposed to include a total of 139 residential units, 36 of these units will be single family detached units, 46 units will be single-family attached units, and the remaining 57 units will be mid-rise condo units. There is the potential that the 57 condo units may instead be 10 townhouse units and two detached units, however for the purposes of this report and to create a conservative analysis, 57 condo units have been considered.

The proposed development will have one full-movement accesses located on Carss Street approximately 150 metres west of Mitcheson Street. Additionally, two future road blocks are proposed, one to the east and one to the future adjacent development to the north.

The subject site is anticipated to be built-out in two phases, with Phase 1 having a build-out year of 2025, and Phase 2 having a build-out year of 2028. Given the minimal number of proposed units, only the future analysis horizon of 2028 will be considered. The analysis will therefore include 2022 existing, 2028 future background, and 2028 future total conditions. The scope of this TIA has been confirmed with staff from both Lanark County and the Municipality of Mississippi Mills in the forms of a Terms of Reference (TOR) document which can be seen in Appendix A.

Figure 1 illustrates the Study Area Context. Figure 2 illustrates the draft plan of subdivision.

Figure 1: Area Context Plan



Figure 2: Draft Plan of Subdivision



EXISTING RESIDENTIAL EAST HALF LOT 18 CONCESSION 9

REGISTERED
"PARK" BLOCK

LANDOWNE STREET
(Approximate Position)
LOT 17 PLAN

6262


(MALLOCH SECTION)

"OTTAWA VALLEY RAIL - TRAIL" (FORMERLY CANADIAN PACIFIC RAILWAY)

SUBJECT TO THE CONDITIONS, IF ANY, SET FORTH IN OUR LETTER DATED _____

THIS DRAFT PLAN IS APPROVED BY THE COUNTY OF LANARK UNDER SECTION 51 OF THE PLANNING ACT. THIS _____ DAY OF _____ 20__.

KURT GREAVES
CHIEF ADMINISTRATIVE OFFICER
COUNTY OF LANARK



DRAFT PLAN OF SUBDIVISION OF PART OF LOT 17 CONCESSION 9
Geographic Township of Ramsay
Municipality of Mississippi Mills
COUNTY OF LANARK
Prepared by Annis, O'Sullivan, Vollebek Ltd.

Scale 1:500
Metric
DISTANCES SHOWN ON THIS PLAN ARE IN METRES AND CAN BE CONVERTED TO FEET BY DIVIDING BY 0.3048

SURVEYOR'S CERTIFICATE
I CERTIFY THAT:
The boundaries of the lands to be subdivided and their relationship to adjoining lands have been accurately and correctly shown.

April 20, 2022
Date
E. H. Herveyer
ONTARIO LAND SURVEYOR

OWNER'S CERTIFICATE
This is to certify that I am the owner / agent of the lands to be subdivided and that this plan was prepared in accordance with my instructions.

April 20, 2022
Date
L. Agganwall
2849358 Ontario Inc.
I have authority to bind the corporation

TABLE TO ILLUSTRATE PROPOSED LAND USE			
PROPOSED USE	LOT / BLOCK	NUMBER OF UNITS	AREA (sqm)
SINGLE DETACHED	1-36	36	26706
MULTI-UNITS RESIDENTIAL BUILDINGS	37-58		16178
RESERVE	59, 60		13
OTHER	61		674
OPEN SPACE/PARKS/ WALKWAYS	62 - 66		14117
STREETS			16034
			TOTAL 73722

ADDITIONAL INFORMATION REQUIRED UNDER SECTION 51-17 OF THE PLANNING ACT
(a) see plan
(b) see plan
(c) see plan
(d) (purpose for which lots are to be used)
(e) see plan
(f) see plan
(g) see plan
(h) Municipality of Mississippi Mills
(i) see soils report
(j) see plan
(k) (municipal services available or to be available)
(l) see plan

1.1 Existing Conditions

1.1.1 Area Road Network

Carss Street

Carss Street is a Municipality of Mississippi Mills minor collector road between Union Street North and Martin Street North, and a Municipality of Mississippi Mills local road west of Union Street North. Carss Street has a two-lane cross-section. No posted speed limit is present, however the Municipality of Mississippi Mills Transportation Master Plan indicates a speed limit of 80 km/h can be assumed for both rural local and rural collector roadways, and a speed limit of 50 km/h can be assumed for both urban local and urban collector roadways. Given Carss Street is a narrow roadway with multiple residential driveways, and is a short roadway segment with a dead-end, a speed limit of 50 km/h has been assumed. Between Martin Street North and the Ottawa Valley Rail Trail, Carss Street is paved, and west of the Ottawa Valley Rail Trail, Carss Street is a gravel road. Grass and gravel shoulders are present on either side of the road with no curbs or gutter provided. The Municipality of Mississippi Mills Transportation Master Plan reserves a minimum 24.0 metre right of way for collector roadways and a 20.0 metre right-of-way for local roadways.

Martin Street North

Martin Street North is a County of Lanark collector road with a two-lane cross-section and a posted speed limit of 60 km/h. Paved shoulders are present north of Carss Street, and gravel shoulders are present south of Carss Street with no curbs or gutters provided. A measured right-of-way taken from the Municipality of Mississippi Mills Mapping Application of 20.0 metres is noted.

Union Street North

Union Street North is a Municipality of Mississippi Mills minor collector road with a two-lane cross-section. No posted speed limit is present, however the Municipality of Mississippi Mills Transportation Master Plan indicates a speed limit of 80 km/h can be assumed for rural collector roadways, and a speed limit of 50 km/h can be assumed for urban collector roadways. Given Union Street is a narrow roadway with multiple residential driveways, has a sidewalk on one side of the road, and is a short roadway segment that ends at Mains Street East, a speed limit of 50 km/h has been assumed. Curbs are presented on both sides of the road south of Brookdale Street. A sidewalk is provided on the east side of the road. The Municipality of Mississippi Mills Transportation Master Plan reserves a minimum 24.0 metre right of way for collector roadways.

1.1.2 Existing Intersections


Carss Street / Martin Street North

The intersection of Carss Street and Martin Street North is an unsignalized three-legged intersection with stop control on the eastbound approach. The northbound approach consists of a shared left-turn / through lane and the southbound approach consists of a shared through / right-turn lane. The eastbound approach has a shared left-turn / right-turn lane. Pedestrian crosswalks are not provided. No turning restrictions were noted at this intersection.



Carss Street / Union Street North

The intersection of Carss Street and Union Street North is an unsignalized three-legged intersection with stop control on the northbound approach. The northbound approach consists of a shared left-turn / right-turn lane. The eastbound approach has a shared through / right-turn lane, and the westbound approach has a shared left-turn / through lane. Pedestrian crosswalks are not provided. No turning restrictions were noted at this intersection.



Carss Street / Ottawa Valley Rail Trail

The Ottawa Valley Rail Trail crosses Carss Street ten metres west of Union Street North. The eastbound through and westbound through vehicle movements on Carss Street are free and are not subject to any type of control. Stop control is provided on the northbound/southbound approach for active transportation.



1.1.3 Existing Driveways

Existing driveways along Carss Street within close proximity to the proposed development’s access are residential in nature and are not expected to generate significant traffic volumes.

1.1.4 Cycling and Pedestrian Facilities

Pedestrian facilities provided within the Study Area are limited to a sidewalk on the east side of Union Street North and to grass, gravel, or paved shoulders. Cycling facilities provided within the Study Area are limited to paved shoulders on Martin Street North north of Carss Street and will need to share the road with vehicles to facilitate cycling trips in all other areas of the Study Area.

The Ottawa Valley Rail Trail is located east of the proposed development and intersects with Carss Street. This trail is approximately 300 kilometres long and provides cycling and pedestrian connections between Smiths Falls and Mattawa and passes through Lanark County. At Carss Street, stop-control signage is noted on the trail on both sides of Carss Street and serves to alert trail users of vehicles on Carss Street. Both Figure 3 and Figure 4 below show the stop-control signage on the trail.

Figure 3: Ottawa Valley Rail Trail - Looking North at Carss Street



Figure 4: Ottawa Valley Rail Trail - Looking South at Carss Street



1.1.5 Existing Transit

There is no existing transit service along the boundary road that would serve the proposed development. Transport Thom bus services provides one trip daily to and from Ottawa. The closest bus stop is located at the intersection of Queen Street and Clyde Street, approximately one kilometre south of the proposed development via the surrounding road network.

1.1.6 Existing Peak Hour Travel Demand

Existing turning movement counts for the weekday AM and PM Peak were provided by Traffic Specialists. Table 1 summarizes the count locations, data sources, and identified peak hour periods.

Table 1: Turning Movement Count Data Dates


Location	Count Date	AM Peak Hour (PM Peak Hour)	Data Source
Carss Street at Martin Street North	Thursday, January 20, 2022	7:30 – 8:30 (16:00 – 17:00)	Traffic Specialists
Carss Street at Union Street North	Wednesday, February 16, 2022	8:45 – 9:45 (15:15 – 16:15)	
Carss and Ottawa Valley Rail Trail	Wednesday, February 16, 2022	8:45 – 9:45 (15:15 – 16:15)	

As all intersections traffic data were collected in 2022, no growth rate is required to be applied to the turning movement counts as they already represent a consistent 2022 horizon. Despite these counts occurring during a time period of minimal COVID-19 restrictions, adjustments are required to account for any impact to these volumes. Using 2016 and 2019 ADT volumes provided by Lanark County staff, a COVID increase factor of 1.5 has been calculated. To calculate this increase factor, the provided ADT volumes have been grown to a 2022 horizon using a compound annual growth rate of 1.5% which was provided by Lanark County staff. The calculations of this adjustment factor can be seen in Appendix B

Additionally, the existing volumes were evaluated for unjustified volume balances greater than 10% and adjusted accordingly to decrease the imbalances to below 10%. Volumes were balanced to the higher observed volume.

Figure 5 illustrates the 2022 existing horizon traffic volumes. Detailed turning movement count data and ADT counts can be found in Appendix C. Based on the existing turning movement counts provided by Traffic Specialists, pedestrian and cycling volumes are noted to be minimal at the Study Area intersections.

Figure 5: 2022 Existing Traffic Volumes



Additionally, volume counts were performed for the Ottawa Valley Rail Trail crossing on Carss Street. All trail users were counted (pedestrians, cyclists, snowmobiles ATVs etc.) and Table 2 below summarizes the collected data.

Table 2: Ottawa Valley Rail Trail Crossing Volume Counts

Time Period	Ottawa Valley Rail Trail Crossing Carss Street
7:00-8:00	4
8:00-9:00	0
9:00-10:00	2
15:00-16:00	0
16:00-17:00	1
17:00-18:00	1
Total	8

As shown above, the volumes on the Ottawa Valley Rail Trail are minimal. Further information can be found in Appendix C.

2 Future Background Conditions

2.1 Planned Conditions

2.1.1 Changes to the Area Transportation Network

The Municipality of Mississippi Mills Active Transportation Plan indicates Martin Street North as a future primary cycling urban route and shows a future proposed sidewalk on Carss Street between Union Street North and Martin Street North. As no specific timing information has been indicated for these improvements, they have been assumed to occur beyond the future analysis horizon.

No other changes to the area transportation network are anticipated.

2.1.2 Other Study Area Developments

At the time of this report, no other development applications were available for the adjacent properties.

2.1.3 Background Growth


A 1.5 % compound annual growth rate was indicated by Lanark County staff to be applied to the existing 2022 traffic counts in order to generate 2028 future background traffic volumes. This growth rate has been applied to all Study Area intersection movements.

2.1.4 Future Background Traffic Volumes

Combining the background growth rate discussed in Section 2.1.3 above, and the 2022 existing traffic volumes, the future background traffic volumes were projected.

Figure 6 illustrates the 2028 future background traffic volumes. All intersection lane configurations have been carried forward from the 2022 existing conditions as there are no anticipated changes for the 2028 horizon.

Figure 6: 2028 Future Background Traffic Volumes



3 Demand Forecasting

3.1 Site Trip Generation

The proposed development will include 36 single family detached units, 46 single-family attached units, and 57 mid-rise multifamily housing units. The *ITE Trip Generation Manual 11th Edition* has been reviewed to determine the appropriate trip generation rate equations for the proposed land uses, and are summarized in Table 3.

Table 3: ITE Trip Generation Rate

Land Use	Data Source	Trip Rates	
		AM Peak	PM Peak
Single Family Detached	LUC 210	$T = 0.91(X) + 0.12$	$T = 0.94(X) + 0.27$
Single Family Attached	LUC 215	$T = 0.52(X) - 5.70$	$T = 0.6(X) - 3.93$
Multifamily Housing (Mid-Rise)	LUC 221	$T = 0.44(X) - 11.61$	$T = 0.39(X) + 0.34$

Notes:
T = Average Vehicle Trip Ends, X = Number of Dwelling Units

Using the above vehicle trip rate equations, the total vehicle trip generation during the weekday AM Peak and weekday PM Peak are summarized in Table 4. Given that the proposed development consists of only residential uses and this analysis is for full occupancy of the subject development, all trips are considered primary, and no synergy or pass-by effects have been considered.

Table 4: Vehicle Site Trip Generation


Land Use	Units	AM Peak (veh/hr)			PM Peak (veh/hr)		
		In	Out	Total	In	Out	Total
Single Family Detached	36	8	22	30	24	14	38
Single Family Attached	46	6	12	18	14	10	24
Multifamily Housing (Mid-Rise)	57	3	10	13	14	9	23
Total		17	44	61	52	33	85

As shown in Table 4, the resulting number of potential new two-way vehicle trips for the proposed development is approximately 61 veh/h during the weekday AM Peak and 85 veh/hr during the weekday PM Peak.

3.2 Vehicle Traffic Distribution and Assignment

Traffic distribution was based on the existing volume splits at Study Area intersections and our knowledge of the surrounding area. Based on this, new site-generated trips were assigned to Study Area intersections, which is illustrated in Figure 7. See Section 5.2 for further information regarding the proposed access configuration.


Figure 7: New Site-Generated Traffic Volumes



3.3 Future Total Travel Demands

The 2028 site generated traffic has been combined with the 2028 future background traffic volumes to estimate the 2028 future total traffic volumes shown in Figure 8. Access configuration details are discussed in Section 5.2.

Figure 8: 2028 Future Total Traffic



4 Operational Analysis

To understand the operational characteristics of the Study Area intersections, a Synchro model has been created using Trafficware’s Synchro (Version 10).

Heavy Vehicle percentages (HV%) have been calculated for each movement based on the existing turning movement counts for the Study Area intersections and have been applied to both the existing and future analysis horizons. Any HV% calculated to be less than 2% was entered as 2% in Synchro to ensure a conservative analysis. At intersections where no Heavy Vehicle percentage is available, 2% has been used. Heavy Vehicle percentage calculations can be found in Appendix D.

Cyclist and pedestrian volumes, where present, were provided for all intersections with turning movement count information collected in 2022 and have been applied to the existing and future conditions analysis. At the site access intersection, a conservative assumption of 5 pedestrians/h and 5 cyclists/h has been used for each intersection leg.

Peak Hour Factors (PHF) have been entered for each intersection based on the turning movement counts provided. The Peak Hour Factors used for each intersection are shown below in Table 5.

Table 5: Peak Hour Factors

Intersection	Peak Hour Factor	
	AM	PM
Carss Street & Martin Street North	0.77	0.91
Carss Street & Union Street North	0.67	0.79
Carss Street & Site Access	0.67*	0.79*

*PHF taken from adjacent intersection of Carss Street & Union Street North

All other parameters have been coded using accepted best practices and default parameters, where applicable.

LOS has been defined using the HCM 2010 definition for LOS at unsignalized intersections in Table 6 below.

Table 6: Level of Service Criteria for Unsignalized Intersections

Delay (s)	LOS
≤10	A
>10 and ≤15	B
>15 and ≤25	C
>25 and ≤35	D
>35 and ≤50	E
>50	F

Critical movements and critical intersections have been defined as individual movements with LOS F or a V/C ratio of 1.00 or greater, and intersections with an overall LOS F. Critical movements and critical intersections will be indicated in red below and require mitigation measures.

4.1 2022 Existing Operational Analysis

Table 7 summarizes the operational analysis for the 2022 existing conditions in both the AM and PM peak periods. Critical movements, as defined above, have been identified in red. Synchro worksheets for the 2022 existing traffic conditions are included in Appendix E.

The Study Area intersections have been designed based on aerial photos and turning lane storage lengths have been rounded to the closest five-metre.

Table 7: 2022 Existing Intersections Operational Analysis

Intersection	Lane	AM Peak Hour				PM Peak Hour			
		LOS	V/C	Delay	Q (95 th)	LOS	V/C	Delay	Q (95 th)
Carss Street / Martin Street North Unsignalized	EBL/R	A	0.02	9.3	0.8	A	0.03	9.8	0.8
	NBL/T	A	0.01	7.6	0.0	A	0.01	7.5	0.0
	SBT/R	-	-	-	-	-	-	-	-
	Overall	A	-	1.1	-	A	-	1.5	-
Carss Street / Union Street North Unsignalized	EBT/R	-	-	-	-	-	-	-	-
	WBL/T	A	0.00	7.3	0.0	A	0.01	7.7	0.0
	NBL/R	A	0.01	8.4	0.0	A	0.02	8.6	0.8
	Overall	A	-	1.6	-	A	-	3.5	-

Generally, the Study Area intersections are shown to operate with good overall LOS and low delays and no identified critical movements (V/C ratio greater than 0.90 or LOS E or worse).

4.2 Future Background Conditions

4.2.1 Future Background Traffic Control Warrants

Using Ontario Traffic Manual (OTM) Book 12 Justification 7 methodology for examining traffic control signal warrants, the unsignalized Study Area intersections have been analyzed. In the future background horizon signalization is not warranted. Traffic control warrant sheets have been included in Appendix F

4.2.2 Future Background Intersection Design

The Ministry of Transportation Ontario (MTO) Geometric Design Standards for Ontario Highways (GDSOH) has been reviewed to determine the need for a northbound left-turn at the two-lane highway unsignalized intersection of Carss Street at Martin Street and a westbound left-turn lane at the two-lane highway unsignalized intersection of Carss Street at Union Street for the future background horizons. Using the GDSOH methodology and appropriate design speeds, it was found that left-turn lanes will not be warranted at either intersection. Left turn lane warrant analysis sheets have been included in Appendix G.

Therefore, all Study Area intersections have been analyzed with the same configuration as shown in existing conditions.

4.2.3 Future Background 2028 Conditions

The 2028 future background intersection volumes have been analyzed to allow for a comparison of the future volumes with and without the proposed development.

Table 8 summarizes the operational analysis for the 2028 future background conditions in both the AM and PM peak periods. Critical movements, as defined above, have been identified in red where applicable. The intersections have been analyzed based on the identified signal control and intersection configurations in Section 4.2.1 and Section 4.2.2, respectively. Synchro worksheets for the 2028 future background traffic conditions are included in Appendix H.

Table 8: 2028 Future Background Conditions Operational Analysis

Intersection	Lane	AM Peak Hour				PM Peak Hour			
		LOS	V/C	Delay	Q (95 th)	LOS	V/C	Delay	Q (95 th)
Carss Street / Martin Street North Unsignalized	EBL/R	A	0.03	9.4	0.8	A	0.03	9.9	0.8
	NBL/T	A	0.01	7.6	0.0	A	0.02	7.5	0.0
	SBT/R	-	-	-	-	-	-	-	-
	Overall	A	-	1.1	-	A	-	1.5	-
Carss Street / Union Street North Unsignalized	EBT/R	-	-	-	-	-	-	-	-
	WBL/T	A	0.00	7.3	0.0	A	0.01	7.7	0.0
	NBL/R	A	0.01	8.4	0.0	A	0.02	8.6	0.8
	Overall	A	-	1.5	-	A	-	3.6	-

Generally, the Study Area intersections are operating in a similar manner to the existing conditions with good overall LOS and low delays and no identified critical movements (V/C ratio greater than 0.90 or LOS E or worse)

4.3 Future Total Conditions

4.3.1 Future Total Traffic Control Warrants

Using Ontario Traffic Manual (OTM) Book 12 Justification 7 methodology for examining traffic control signal warrants the unsignalized Study Area intersections, as well as the intersection of Site Access #1 and Carss Street have been analyzed. In the future total horizon signalization is not warranted. Traffic control warrant sheets have been included in Appendix F.

4.3.2 Future Total Intersection Design

The Ministry of Transportation Ontario (MTO) Geometric Design Standards for Ontario Highways (GDSOH) has been reviewed to determine the need for a northbound left-turn at the two-lane highway unsignalized intersection of Carss Street at Martin Street and a westbound left-turn lane at the two-lane highway unsignalized intersection of Carss Street at Union Street for the future total horizons. Using the GDSOH methodology and appropriate design speeds, it was found that left-turn lanes will not be warranted at either intersection. Left turn lane warrant analysis sheets have been included in Appendix G. Therefore, all Study Area intersections have been analyzed with the same configuration as shown in existing conditions.

A left-turn lane warrant analysis has not been performed for the eastbound left-turn movement into the site access intersection. This is because vehicles are not expected to turn left into the subject development as Carss Street is a dead-end to the west of the site access intersection.

4.3.3 Future Total 2028 Conditions

The proposed development’s trip generation has been added to the 2028 future background traffic volumes to project the impact of the new traffic on the future road network.

Table 9 summarizes the operational analysis for the 2028 future total conditions in both the AM and PM peak periods. Critical movements, as defined above, have been identified in red where applicable. The intersections have been analyzed based on the identified signal control and intersection configurations in Section 4.3.1 and Section 4.3.2, respectively. Synchro worksheets for the 2028 future total traffic conditions are included in Appendix I.

Table 9: 2028 Future Total Conditions Operational Analysis

Intersection	Lane	AM Peak Hour				PM Peak Hour			
		LOS	V/C	Delay	Q (95 th)	LOS	V/C	Delay	Q (95 th)
Carss Street / Martin Street North Unsignalized	EBL/R	A	0.08	9.8	2.3	B	0.08	10.6	1.5
	NBL/T	A	0.02	7.6	0.8	A	0.04	7.6	0.8
	SBT/R	-	-	-	-	-	-	-	-
	Overall	A	-	2.6	-	A	-	2.9	-
Carss Street / Union Street North Unsignalized	EBT/R	-	-	-	-	-	-	-	-
	WBL/T	A	0.00	7.4	0.0	A	0.01	7.8	0.0
	NBL/R	A	0.01	8.7	0.0	A	0.05	9.2	1.5
	Overall	A	-	0.5	-	A	-	2.5	-
Site Access #1 / Carss Street Unsignalized	EBL/T	A	-	0.0	0.0	A	-	0.0	0.0
	WBT/R	-	-	-	-	-	-	-	-
	SBL/R	A	0.07	9.1	1.5	A	0.05	9.2	0.8
	Overall	A	-	4.6	-	A	-	2.4	-

Generally, the Study Area intersections are shown to operate in a similar manner to the 2028 future background conditions with good overall LOS and low delays and no identified critical movements (V/C ratio greater than 0.90 or LOS E or worse). This indicates that the addition of site traffic from the proposed development will have a minimal impact on the Study Area intersection and therefore no mitigation is required.

It is noted that the site is anticipated to generate additional low volumes on Carss Street. Given the low crossing volumes on Carss Street at the Ottawa Valley Rail Trail and the stop control provided on the trail for active transportation, the addition of site traffic is not expected to have a negative impact at this crossing. Based on this, no additional signage or traffic control measures are required on Carss Street at this crossing.

5 Site Plan Review

This section provides an overview of site accesses, site circulation, parking and active mode facilities. The proposed concept Site Plan was previously illustrated in Figure 2.

5.1 Site Circulation

At this time, the Site Plan may be subject to future design changes and as such is to be considered a high-level depiction of the planned development. Therefore, the geometry and analysis of the site access will be refined at the Site Plan approval stage to ensure safe fire routes and servicing access.

5.2 Site Access

The proposed development will be an unsignalized full movement access on Carss Street approximately 150 metres west of Mitcheson Street.

As discussed above, a signal warrant analysis has been conducted for the 2028 future total horizon using the OTM Book 12 Justification 7 criteria. Using this criteria, it was found that a signal is not warranted at the site access intersection. Appendix E includes the signal warrants for the access.

The volume on the eastbound left-turn movement at the site access intersection is zero as Carss Street is a dead-end to the west of the site access intersection. Therefore, no left-turn lane warrant has been examined at the access.

5.3 Parking Supply

The required parking is subject to Municipality of Mississippi Mills Zoning By-Law #11-83, 2020, and will be provided accordingly. The parking supply will be further examined at the site plan application stage.

5.4 Active Mode Considerations

The proposed development will provide active mode facilities and connections within the development as well as connections to the surrounding road and trail network in the Study Area. Pedestrian facilities will be provided within the proposed development along one side of the private access roads with direct connections to all residential buildings and parking spaces. These pedestrian facilities will also connect to the Ottawa Valley Rail Trail via a walkway and trails to the west.

The active mode facilities can be seen in Figure 2 and will encourage pedestrian traffic within the proposed development as well as within the overall Study Area.

6 Findings and Recommendations

- a) The Hilan Village development includes 36 single family detached units, 46 single-family attached units, and 57 units mid-rise condo units.
- b) The proposed development will have an unsignalized access located on Carss Street.
- c) The full build-out horizon year of 2028 has been analyzed.
- d) No significant planned changes to area transportation network have been noted and no surrounding background developments have been considered.
- e) The proposed development is projected to generate 61 veh/h during the weekday AM Peak and 85 veh/hr during the weekday PM Peak.
- f) A 1.5% compound annual growth rate was selected to generate the 2028 future background traffic volumes.

- g) Using the existing 2022 traffic volumes, adjusted for the impact of COVID-19, an operational analysis of existing conditions was undertaken. As no high v/c ratios or high delays were noted, no mitigation measures were recommended.
- h) The 2028 future background traffic volumes, including the background growth was analyzed. It was found that turning movements operate with reasonable LOS and delay and in a similar manner as existing conditions.
- i) With the addition of site traffic volumes to the Study Area intersections, the intersections operate with minimally worse LOS and higher delays in the 2028 future horizon. These changes are minor and do not cause critical movements. Additionally, the site access intersection operates well with no required mitigation measures.
- j) The vehicle trips generated by the subject site are anticipated to have a negligible impact on the Ottawa Valley Rail Trail crossing on Carss Street given the low crossing volumes and stop control provided on approaches for active transportation. Based on this, no additional signage or traffic control measures are required on Carss Street at this crossing.
- k) Traffic volumes within the Study Area are relatively low, and as such, signalization is not warranted at unsignalized intersections at any analysis horizon.
- l) Traffic volumes within the Study Area are relatively low, and as such, left-turn lanes are not warranted at the intersection of Martin Street North and Carss Street or at the intersection Union Street North and Carss Street.
- m) The required parking will be provided in accordance with the requirements outlined in the Municipality of Mississippi Mills Zoning By-Law and will be further examined at the site plan application stage.
- n) The proposed development will encourage active transportation through the provision of active mode facilities on-site and through connections to the surrounding Study Area transportation network.

The Hilan Village development will have a minor impact on the Study Area road network. The proposed access will operate with reasonable LOS and delay on the turning movements into and out of the site. Additionally, through the provision of on-site facilities, this development will be supportive of active mode transportation. It is recommended that, from a transportation perspective, the proposed development application proceed.

Prepared By:

Reviewed By:



Yu-Chu Chen, E.I.T.
343-777-2426
Michelle.Chen@CGHTransportation.com



Mark Crockford, P. Eng.
905-251-4070
Mark.Crockford@CGHTransportation.com

Appendix A

Terms of Reference (TOR)



Technical Memorandum

To:	Sean Derouin & Terry McCann – Lanark County Cory Smith – Municipality of Mississippi Mills	Date:	2022-02-02
Cc:	Mark Crockford – CGH Transportation Adam O’Connor – Keeper Co.		
From:	Robin Marinac	Project Number:	2021-133

Re: Hilan Village TOR - Terms of Reference

We have been asked to undertake the scoped Transportation Impact Assessment to support the proposed development of Hilan Village in the Ward of Almonte, located at the northwest corner of Carss Street and the Ottawa Valley Recreational Trail and is currently designated as a Development (D2) Zone. The site is proposed to include a minimum of 94 residential units, and a maximum of 125 residential units. While it is unlikely that the maximum number of residential units will be 125, this scenario has still been evaluated below to ensure a conservative analysis is provided. The proposed development is anticipated to have a full build-out and occupancy year of 2028.

The primary site access is located on Carss Street approximately 150 metres west of Mitcheson Street, and a secondary access to the future adjacent development to the north is proposed. This access to the north is dependent on development by others and is considered to be part of the ultimate design of the proposed development. The site plan can be seen in Attachment 1.

We have prepared the following scope of work for review and endorsement. Please let us know if you have any comments or additions. All data requests are noted in *red* and have also been summarized at the end of the memo.

Scoped Transportation Impact Assessment Requirements (TIA):

The study will be in accordance with the *Institute of Transportation Engineers Transportation Impact Analyses for Site Development* as well as *Section 4.6.12 Traffic Impact Assessment* within the *Municipality of Mississippi Mills Community Official Plan*. As fewer than 100 peak period vehicle trips are anticipated to be generated by the proposed development, based on the ITE guidelines, a scoped TIS is considered sufficient to support the proposed development.

Study Area:

- An overview of the transportation system existing conditions will be documented (including transit, cycling, pedestrian and automobile modes).
- A summary of existing transportation policies within the Study Area will be identified.
- An overview of the Study Area road network will be provided including the road classification and descriptions of:
 - Carss Street

- Martin Street North

The following intersections will be included in the scoped Transportation Impact Assessment:

- Carss Street and Martin Street North
- All proposed Site Accesses (two accesses assumed – one on Carss Street, one to the north to future development)

Existing Traffic Data:

- As Turning Movement Counts (TMCs) are unavailable at the intersection of Carss Street and Martin Street North, current TMCs will be collected by a third-party consultant.
 - Given the current COVID-19 related restrictions, the collected intersection data will be compared and if needed, factored based on previously collected 2015 data shown in the Municipality of Mississippi Mills Comprehensive Transportation Master Plan (2016).
 - Please provide the 2015 volume data collected on Martin Street North. *(Data request)*
- A compound annual growth rate of 1.5%, as indicated by Lanark County staff, will be applied to all turning movements of the Study Area intersection to determine the 2022 existing traffic volumes.
- Collision data has not been requested as Lanark County staff have indicated no collisions are present in the Study Area.

Study Horizon and Peak Periods:

- Base year 2022, followed by a build-out future horizon of 2028.
- AM and PM peak hours for all horizons.

Background Growth:

- A compound annual growth rate of 1.5%, as indicated by Lanark County staff, will be applied to all turning movements of the Study Area intersection to determine the 2028 background traffic volumes.
- Surrounding development traffic impact assessments and reports will be used as reference to confirm identify additional growth from surrounding developments in the area. Any relevant reports are requested. *(Data request)*

Changes to Area Transportation Network:

- The Municipality of Mississippi Mills Active Transportation Plan indicates Martin Street North as a future primary cycling urban route. As no specific timing information has been indicated for this improvement, it has been assumed to occur beyond the future analysis horizons. Please provide additional timing information if this is not the case. *(Data request)*
- The Municipality of Mississippi Mills Active Transportation Plan indicates a future proposed sidewalk on Carss Street between Union Street North and Martin Street North. As no specific timing information has been indicated for this improvement, it has been assumed to occur beyond the future analysis horizons. Please provide additional timing information if this is not the case. *(Data request)*
- The Municipality of Mississippi Mills Active Transportation Plan indicates a future multi-use pathway on the Ottawa Valley Rail Trail north of the proposed development. As no specific timing information has been indicated for this improvement, it has been assumed to occur beyond the future analysis horizons. Please provide additional timing information if this is not the case. *(Data request)*

Development Site Traffic:

- Trip generation: ITE Trip Generation Manual 11th Edition.
- Existing Modal Split: If applicable, please provide modal splits to be used. *(Data request)*
- Trip distribution and assignment of auto trips: Surrounding area characteristics.

Traffic Analysis:

- Traffic analysis to be performed using Synchro 10 on Study Area network intersections to determine the LOS, delay, V / C ratio and the 95th percentile queues for overall intersections as well as individual movements using Highway Capacity Manual 2010 (HCM) methodology
 - Heavy Vehicle %, pedestrian volumes, and cyclist volumes will be taken from the collected TMC data. Where information is not available, a pedestrian volume of 5 pedestrians/hour, a cyclist volume of 5 cyclists/hour, and a Heavy Vehicle % of 2% will be used.
 - Other Synchro inputs will be based on site observations and Synchro default parameters.
- A qualitative transit, cycling, and pedestrian analysis including consideration of any planned improvements
- Qualitative access location analysis and site review where necessary

Recommendations:


- Any recommended offsite and onsite improvements or mitigation measures, which may include turn lane requirements, pedestrian / cycling / transit amenities, TDM measures, construction impacts, safety measures etc.

The following is a list of requested information, some of which has been indicated in *red* above, that we are requesting to inform the Scoped TIS:

- Any other guidelines you would like us to consider
- 2015 volume counts on Martin Street South, as referenced in the Municipality of Mississippi Mills Comprehensive Transportation Master Plan (2016)
- Any relevant developments that may influence the background growth within the proposed Study Area
- Specific changes to the Study Area Road network that you would like us to consider

Attachment 1

Site Plan



CONCEPT PLAN SITE STATS

- LINEAR FRONTAGE = 1,163m (3816 ft)
- UNIT COUNT = 125 (94 w/o Condo)
- GROSS SITE AREA = 73,740m² / 7.374ha / 18.22ac
- NET SITE AREA (Excl. Slope Lands) = 52,492m² / 5.25ha / 12.97ac
- GROSS AREA FOR USES:
 - RESIDENTIAL = 33,834m²
 - ROAD ALLOWANCES = 14,568m²
 - PARK & GROVES = 4,090m²
 - SLOPED HAZARD LANDS = 21,248m²

<p>GENERAL REVIEW</p> <p>no. date revision</p>	
<p>It is the responsibility of the appropriate contractor to check and verify all dimensions on site and report all errors and/or omissions to the architect.</p> <p>All contractors must comply with all pertinent codes and by-laws.</p> <p>Do not scale drawings.</p> <p>This drawing may not be used for construction until signed.</p> <p>Copyright reserved.</p>	
<p>Hobin Architecture Incorporated</p> <p>63 Pamela Street Ottawa, Ontario Canada K1S 3K7 T: 613-238-7200 F: 613-235-2005 E: mail@hobinarc.com hobinarc.com</p>	
<p>PROJECT/LOCATION: 38 CARRS ST ALMONTE ONTARIO</p>	
<p>DRAWING TITLE: SITE PLAN</p>	
<p>DRAWN BY: TD</p>	<p>DATE: DEC. 2021</p>
<p>SCALE: 1:600</p>	
<p>PROJECT: 2122</p>	
<p>DRAWING NO.:</p>	
<p>SP-1</p>	
<p>REVISION NO.:</p>	

Note:
 HILAN ALMONTE SITE PLAN

Robin Marinac

From: Terry McCann <TMcCann@lanarkcounty.ca>
Sent: March 8, 2022 2:07 PM
To: Robin Marinac
Subject: RE: Hilan Village Transportation Impact Assessment Terms of Reference Scoping Document

Robin
Please proceed as outlined below
Thanks


Terry McCann
E: tmccann@lanarkcounty.ca

From: Robin Marinac <robin.marinac@cghtransportation.com>
Sent: March 8, 2022 2:04 PM
To: Terry McCann <TMcCann@lanarkcounty.ca>
Cc: Michelle Chen <michelle.chen@cghtransportation.com>
Subject: RE: Hilan Village Transportation Impact Assessment Terms of Reference Scoping Document

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

Hi Terry,

Below is a screenshot of the Mississippi Mills TMP 2015 AM Peak volumes. I've circled the volumes of interest.



As you can see, these volumes are not as close to the intersections of interest and have multiple residential roads that will act as traffic generators and contribute to an inaccurate adjustment factor when compared to the ADT volumes you provided us with. At the time of the TOR, these ADT volumes had not been sent to us yet so the 2015 TMP volumes

were the best (and only) option. Now that we have the ADT volumes from 2016 and 2019 (2021 will not be used as it was taken during COVID) we have determined these volumes to be more applicable for our uses as they were taken on Martin Street close to Brookdale Street which is much closer to Carss Street, were collected more recently than the 2015 volumes, and also provide PM peak volumes for comparison whereas the TMP does not. It is noted that the 2016 and 2019 ADT counts will be grown to a 2022 horizon to allow for a proper volume comparison.

The 2016 ADT volumes are shown here:

Average Daily Volume							
	Mon	Tue	Wed	Thu	Fri	Sat	Sun
North	0	874	839	906	0	0	0
South	0	791	777	837	0	0	0
Combined	0	1665	1616	1743	0	0	0
AM Pk North	-	65	49	59	-	-	-
PM Pk North	-	102	85	94	-	-	-
AM Pk South	-	79	77	83	-	-	-
PM Pk South	-	62	61	68	-	-	-
Days	-	1	1	1	-	-	-

Report created 16:21 Monday, June 06, 2016 using MTE version 4.0.6.0

The 2019 ADT volumes are shown here:

Average Daily Volume							
	Mon	Tue	Wed	Thu	Fri	Sat	Sun
North	0	944	924	841	0	0	0
South	0	872	850	766	0	0	0
Combined	0	1816	1774	1607	0	0	0
AM Pk North	-	64	57	52	-	-	-
PM Pk North	-	117	97	84	-	-	-
AM Pk South	-	63	72	66	-	-	-
PM Pk South	-	71	63	56	-	-	-
Days	-	1	1	1	-	-	-

Report created 13:17 Thursday, October 10, 2019 using MTE version 4.0.6.0

Kind regards,
Robin Marinac



Robin Marinac, EIT
CGH Transportation Inc.
 P: 437-242-5183
 E: robin.marinac@cghtransportation.com

From: Terry McCann <TMcCann@lanarkcounty.ca>
Sent: March 8, 2022 12:14 PM
To: Robin Marinac <robin.marinac@cghtransportation.com>

Cc: Michelle Chen <michelle.chen@cghtransportation.com>
Subject: RE: Hilan Village Transportation Impact Assessment Terms of Reference Scoping Document

Robin
Without me looking it up what were the numbers for 2015 compared to the data we sent you ?

Terry McCann
E: tmccann@lanarkcounty.ca

From: Robin Marinac <robin.marinac@cghtransportation.com>
Sent: March 8, 2022 11:25 AM
To: Terry McCann <TMcCann@lanarkcounty.ca>
Cc: Michelle Chen <michelle.chen@cghtransportation.com>
Subject: RE: Hilan Village Transportation Impact Assessment Terms of Reference Scoping Document

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

Hi Terry,

I just wanted to follow up on our phone conversation a couple weeks ago where you provided your approval for our TOR with the requests that we examine the implications of development traffic on the Ottawa Valley Rail Trail crossing on Carss Street, as well as amend our description of the trail.

One change to the TOR that we have made since your approval is with respect to the calculation of the COVID-19 adjustment factor. In our TOR we indicated that should an adjustment factor be required, it would be calculated using the 2015 AM peak hour data shown in the Municipality of Mississippi Mills Comprehensive Transportation Master Plan. We have since received the ADTs from you for Martin Street North that were collected more recently than what is shown in the TMP. Additionally, these ADTs provide us with PM peak period information as well and are located closer to our Study Area intersections of interest. As such, we are proposing to use a COVID-19 adjustment factor calculated based on the ADTs that you sent as opposed to the TMP volumes originally discussed in the TOR. The adjustment factor will be applied to both Study Area intersections. Please advise if this approach is acceptable to you and we will proceed.

Kind regards,
Robin Marinac



Robin Marinac, EIT
CGH Transportation Inc.
P: 437-242-5183
E: robin.marinac@cghtransportation.com

From: Robin Marinac
Sent: February 2, 2022 11:09 AM
To: 'Sean Derouin' <SDerouin@lanarkcounty.ca>; 'Terry McCann' <TMcCann@lanarkcounty.ca>; 'csmith@mississippimills.ca' <csmith@mississippimills.ca>
Cc: 'keeper.co.ltd@gmail.com' <keeper.co.ltd@gmail.com>; Mark Crockford <mark.crockford@cghtransportation.com>
Subject: RE: Hilan Village Transportation Impact Assessment Terms of Reference Scoping Document

Hi all,

I have re-attached the TOR for your review as the previous version did not contain Attachment 1. Apologies for any confusion this may have caused.

Kind regards,
Robin Marinac



Robin Marinac, EIT
CGH Transportation Inc.
P: 437-242-5183
E: robin.marinac@cghtransportation.com

From: Robin Marinac
Sent: February 2, 2022 10:46 AM
To: Sean Derouin <SDerouin@lanarkcounty.ca>; Terry McCann <TMcCann@lanarkcounty.ca>;
csmith@mississippimills.ca
Cc: keeper.co.ltd@gmail.com; Mark Crockford <mark.crockford@cghtransportation.com>
Subject: Hilan Village Transportation Impact Assessment Terms of Reference Scoping Document

Hi Cory, Sean, and Terry,

Please find attached our Hilan Village Transportation Impact Assessment Terms of Reference (TOR) for your review. Please let us know if you have any comments or questions as we would like to ensure that our TOR reflects the appropriate scope of work to support the proposed development.

Kind regards,
Robin Marinac



Robin Marinac, EIT
CGH Transportation Inc.
P: 437-242-5183
E: robin.marinac@cghtransportation.com

Robin Marinac

From: Robin Marinac
Sent: March 29, 2022 8:34 AM
To: Cory Smith
Cc: Michelle Chen
Subject: RE: Hilan Village Transportation Impact Assessment Terms of Reference Scoping Document

Hi Cory,

We are finishing up our traffic report and I realized I forgot to follow up with you and thank you for taking the time to discuss and approve our amended approach to calculating a COVID-19 adjustment factor, as well as confirming no background studies are to be included. We appreciate you taking the time to speak with us earlier this month.

Kind regards,
Robin Marinac



Robin Marinac, EIT
CGH Transportation Inc.
P: 437-242-5183
E: robin.marinac@cghtransportation.com

From: Robin Marinac
Sent: March 8, 2022 5:15 PM
To: Cory Smith <csmith@mississippimills.ca>
Cc: Mark Crockford <mark.crockford@cghtransportation.com>; Michelle Chen <michelle.chen@cghtransportation.com>
Subject: RE: Hilan Village Transportation Impact Assessment Terms of Reference Scoping Document

Hi Cory,

9:00 am tomorrow sounds great. I'll send you a Microsoft Teams invitation shortly.

Kind regards,
Robin Marinac



Robin Marinac, EIT
CGH Transportation Inc.
P: 437-242-5183
E: robin.marinac@cghtransportation.com

From: Cory Smith <csmith@mississippimills.ca>
Sent: March 8, 2022 3:01 PM
To: Robin Marinac <robin.marinac@cghtransportation.com>
Cc: Mark Crockford <mark.crockford@cghtransportation.com>; Michelle Chen <michelle.chen@cghtransportation.com>
Subject: RE: Hilan Village Transportation Impact Assessment Terms of Reference Scoping Document

Perhaps we can talk tomorrow at 9:00am

Regards,

Cory Smith, C.Tech.

A/Director of Roads and Public Works
Municipality of Mississippi Mills
3131 Old Perth Rd.
P.O. Box 400
Almonte, ON
K0A 1A0
csmith@mississippimills.ca
(613)256-2064 x229

From: Robin Marinac <robin.marinac@cghtransportation.com>
Sent: March 8, 2022 2:11 PM
To: Cory Smith <csmith@mississippimills.ca>
Cc: Mark Crockford <mark.crockford@cghtransportation.com>; Michelle Chen <michelle.chen@cghtransportation.com>
Subject: RE: Hilan Village Transportation Impact Assessment Terms of Reference Scoping Document

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

Hi Cory,

I just wanted to follow up on my phone call and message regarding availability of traffic reports for the surrounding background developments mentioned below, as well as an amendment to our TOR.

Since receiving your approval on our TOR we have received additional ADT data on Martin Street that changes our proposed approach to calculating the COVID-19 adjustment factor. In our TOR we indicated that should an adjustment factor be required, it would be calculated using the 2015 AM peak hour data shown in the Municipality of Mississippi Mills Comprehensive Transportation Master Plan. We have since received the ADTs from Terry McCann at Lanark County that were collected more recently than what is shown in the TMP. Additionally, these ADTs provide us with PM peak period information as well and are located closer to our Study Area intersections of interest. As such, we are proposing to use a COVID-19 adjustment factor calculated based on the ADTs that were provided as opposed to the TMP volumes originally discussed in the TOR. The adjustment factor will be applied to both Study Area intersections. Please advise if this approach is acceptable to you and we will proceed.

Kind regards,
Robin Marinac



Robin Marinac, EIT
CGH Transportation Inc.
P: 437-242-5183
E: robin.marinac@cghtransportation.com

From: Robin Marinac
Sent: March 2, 2022 9:11 AM
To: Cory Smith <csmith@mississippimills.ca>

Cc: Mark Crockford <mark.crockford@cghtransportation.com>

Subject: RE: Hilan Village Transportation Impact Assessment Terms of Reference Scoping Document

Hi Cory,

I just wanted to follow up on my request for any traffic studies we can use to account for the traffic generated by the future developments listed below. Without these we will have to assume that the traffic generated by these future developments is accounted for in the compound annual growth rate applied at our Study Area intersections. Please indicate if there are any available studies for use, or if accounting for these background developments using the compound annual growth rate applied to our Study Area intersections is acceptable.

Kind regards,
Robin Marinac



Robin Marinac, EIT
CGH Transportation Inc.
P: 437-242-5183
E: robin.marinac@cghtransportation.com

From: Cory Smith <csmith@mississippimills.ca>

Sent: February 8, 2022 1:01 PM

To: Robin Marinac <robin.marinac@cghtransportation.com>; Sean Derouin <SDerouin@lanarkcounty.ca>; Terry McCann <TMcCann@lanarkcounty.ca>

Cc: keeper.co.ltd@gmail.com; Mark Crockford <mark.crockford@cghtransportation.com>

Subject: RE: Hilan Village Transportation Impact Assessment Terms of Reference Scoping Document

We do not have traffic counts in that area newer than the years referenced in you TOR. It is important to maintain linkages to the unopened Lansdowne Road allowance and the adjacent property that is in the urban boundary. In addition, the intersection of Carss and Union should be looked at with consideration for the OVRT being right there.

There are future developments to the northeast directly above Mitcheson, with Mitcheson being extended to Lansdowne. Directly across Carss there will be a large facility developed as well. And the property to the north needs to have accessibility maintained for future development.

Regards,

Cory Smith, C.Tech.

A/Director of Roads and Public Works

Municipality of Mississippi Mills

3131 Old Perth Rd.

P.O. Box 400

Almonte, ON

K0A 1A0

csmith@mississippimills.ca

(613)256-2064 x229

From: Robin Marinac <robin.marinac@cghtransportation.com>

Sent: February 2, 2022 11:09 AM

To: Sean Derouin <SDerouin@lanarkcounty.ca>; Terry McCann <TMcCann@lanarkcounty.ca>; Cory Smith <csmith@mississippimills.ca>
Cc: keeper.co.ltd@gmail.com; Mark Crockford <mark.crockford@cghtransportation.com>
Subject: RE: Hilan Village Transportation Impact Assessment Terms of Reference Scoping Document

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

Hi all,

I have re-attached the TOR for your review as the previous version did not contain Attachment 1. Apologies for any confusion this may have caused.

Kind regards,
Robin Marinac



Robin Marinac, EIT
CGH Transportation Inc.
P: 437-242-5183
E: robin.marinac@cghtransportation.com

From: Robin Marinac
Sent: February 2, 2022 10:46 AM
To: Sean Derouin <SDerouin@lanarkcounty.ca>; Terry McCann <TMcCann@lanarkcounty.ca>; csmith@mississippimills.ca
Cc: keeper.co.ltd@gmail.com; Mark Crockford <mark.crockford@cghtransportation.com>
Subject: Hilan Village Transportation Impact Assessment Terms of Reference Scoping Document

Hi Cory, Sean, and Terry,

Please find attached our Hilan Village Transportation Impact Assessment Terms of Reference (TOR) for your review. Please let us know if you have any comments or questions as we would like to ensure that our TOR reflects the appropriate scope of work to support the proposed development.

Kind regards,
Robin Marinac



Robin Marinac, EIT
CGH Transportation Inc.
P: 437-242-5183
E: robin.marinac@cghtransportation.com

Appendix B

Adjustment Factor

Carss Street / Martin Street N											
NBL	NBT	NBR	WBL	WBT	WBR	SBL	SBT	SBR	EBL	EBT	EBR
7	39	0	0	0	2	0	77	2	2	0	8
12	60	0	0	0	2	0	63	2	5	0	8

2016 ADT Martin St btwn Ottawa St & Brookdale St		
	NB	SB
AM	64	63
PM	117	71

2019 ADT Martin St btwn Ottawa St & Brookdale St		
	NB	SB
AM	65	79
PM	102	62

2022 ADT Martin St btwn Ottawa St & Brookdale St		
	NB	SB
AM	70	69
PM	128	78

2022 ADT Martin St btwn Ottawa St & Brookdale St		
	NB	SB
AM	68	83
PM	104	65

North of Carss		
	NB	SB
	Carss Street / Martin Street N	
AM	41	79
PM	65	65

South of Carss		
	NB	SB
	Carss Street / Martin Street N	
AM	46	85
PM	72	71

	NB	SB	Average		
ADT AM	1.52	0.98	1.25		
ADT PM	1.78	1.10	1.44	Use:	1.50

Traffic Summary

Station # - HF44807F, Cr17 017229 Ottawa Street to Brookdale Street

Date - 0:00 Tuesday, May 03, 2016 to 0:00 Friday, May 06, 2016 (3 days of data)

Volume						
	Total	Weekday	Weekend	ADT	AWDT	AWET
Combined	5024	5024	0	1675	1675	0
North	2619	2619	0	873	873	0
South	2405	2405	0	802	802	0
Days	3	3	-	3	3	-

Speed				
	All Days	Weekdays	Weekend	
Mean speed	50.5	50.5	-	km/h
Median speed	51.1	51.1	-	km/h
85% speed	60.1	60.1	-	km/h

PSL = 60 km/h

Class				
Class (Scheme F3)	All Days	%	Weekdays	Weekend
1 - CYCLE	42	0.8%	42	0
2 - PC	3593	71.5%	3593	0
3 - 2A-4T	1195	23.8%	1195	0
4 - BUS	43	0.9%	43	0
5 - 2A-6T	57	1.1%	57	0
6 - 3A-SU	72	1.4%	72	0
7 - 4A-SU	3	0.1%	3	0
8 - <5A DBL	1	0.0%	1	0
9 - 5A DBL	3	0.1%	3	0
10 - >6A DBL	15	0.3%	15	0
11 - <6A MULTI	0	0.0%	0	0
12 - 6A MULTI	0	0.0%	0	0
13 - >6A MULTI	0	0.0%	0	0

Average Daily Volume							
	Mon	Tue	Wed	Thu	Fri	Sat	Sun
North	0	874	839	906	0	0	0
South	0	791	777	837	0	0	0
Combined	0	1665	1616	1743	0	0	0
AM Pk North	-	65	49	59	-	-	-
PM Pk North	-	102	85	94	-	-	-
AM Pk South	-	79	77	83	-	-	-
PM Pk South	-	62	61	68	-	-	-
Days	-	1	1	1	-	-	-

Traffic Summary

Station # - FJ199DQZ, Cr 17 017229 Ottawa Street to Brookdale Street

Date - Tuesday, July 09, 2019 to Friday, July 12, 2019 (3 days of data)

Volume						
	Total	Weekday	Weekend	ADT	AWDT	AWET
Combined	5197	5197	0	1732	1732	0
North	2709	2709	0	903	903	0
South	2488	2488	0	829	829	0
Days	3	3	-	3	3	-

Speed				
	All Days	Weekdays	Weekend	
Mean speed	53.6	53.6	-	km/h
Median speed	54.4	54.4	-	km/h
85% speed	63.7	63.7	-	km/h

PSL = 60 km/h

Class				
Class (Scheme F3)	All Days	%	Weekdays	Weekend
1 - CYCLE	76	1.5%	76	0
2 - PC	3768	72.5%	3768	0
3 - 2A-4T	1184	22.8%	1184	0
4 - BUS	21	0.4%	21	0
5 - 2A-6T	108	2.1%	108	0
6 - 3A-SU	30	0.6%	30	0
7 - 4A-SU	3	0.1%	3	0
8 - <5A DBL	3	0.1%	3	0
9 - 5A DBL	1	0.0%	1	0
10 - >6A DBL	3	0.1%	3	0
11 - <6A MULTI	0	0.0%	0	0
12 - 6A MULTI	0	0.0%	0	0
13 - >6A MULTI	0	0.0%	0	0

Average Daily Volume							
	Mon	Tue	Wed	Thu	Fri	Sat	Sun
North	0	944	924	841	0	0	0
South	0	872	850	766	0	0	0
Combined	0	1816	1774	1607	0	0	0
AM Pk North	-	64	57	52	-	-	-
PM Pk North	-	117	97	84	-	-	-
AM Pk South	-	63	72	66	-	-	-
PM Pk South	-	71	63	56	-	-	-
Days	-	1	1	1	-	-	-

Appendix C


Traffic Data



Turning Movement Count Bicycle Summary Flow Diagram



Carss Street & Martin Street North Almonte, ON





Time Period	Carss St. Eastbound				N/A Westbound				Martin St. (N) Northbound				Martin St. (N) Southbound				GR Tot					
	LT	ST	RT	UT	LT	ST	RT	UT	LT	ST	RT	UT	LT	ST	RT	UT						
0700-0800	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
0800-0900	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
0900-1000	0	0	0	0	No bicycles observed.				0	0	0	0	0	0	0	0	0	0	0			
1500-1600	0	0	0	0					0	0	0	0	0	0	0	0	0	0	0	0	0	0
1600-1700	0	0	0	0					0	0	0	0	0	0	0	0	0	0	0	0	0	0
1700-1800	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
Totals	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			



Turning Movement Count Summary, AM and PM Peak Hour Flow Diagrams All Vehicles Except Bicycles



Carss Street & Martin Street North Almonte, ON






Turning Movement Count Heavy Vehicle Summary Flow Diagram



Turning Movement Count Pedestrian Crossings Summary and Flow Diagram




Carss Street & Martin Street North Almonte, ON



Time Period	Carss St.				N/A				Martin St. (N)				Martin St. (N)							
	Eastbound		Westbound		Northbound		Southbound		Eastbound		Westbound		Northbound		Southbound					
	LT	ST	RT	UT	LT	ST	RT	UT	LT	ST	RT	UT	LT	ST	RT	UT				
0700-0800	0	0	0	0	0	0	0	0	0	1	0	0	0	1	4	0	0	4	0	0
0800-0900	0	0	1	0	0	0	0	0	0	4	0	0	0	4	1	0	0	1	0	0
0900-1000	0	0	0	0	0	0	0	0	0	2	0	0	0	2	3	1	0	4	0	0
1500-1600	3	1	1	0	4	0	0	0	1	3	0	0	4	5	0	0	5	13	0	0
1600-1700	0	0	1	0	1	0	0	0	0	1	0	0	1	1	1	0	2	4	0	0
1700-1800	0	0	1	0	1	0	0	0	0	1	0	0	1	0	1	0	1	3	0	0
Totals	3	1	2	0	5	0	0	0	1	5	0	0	6	14	1	1	17	37	0	0

Carss Street & Martin Street North Almonte, ON



Time Period	West Side Crossing Carss St.	East Side Crossing N/A	Street Total	South Side Crossing Martin St. (N)	North Side Crossing Martin St. (N)	Street Total	Grand Total
0700-0800	1		1	0	0	0	1
0800-0900	1		1	1	0	1	2
0900-1000	0		0	0	0	0	0
1500-1600	0		0	0	0	0	0
1600-1700	0		0	0	0	0	0
1700-1800	0		0	0	0	0	0
Totals	2		2	1	0	1	3

Comments:
Traffic count was conducted during the SARS-CoV-2 (Covid-19) pandemic. All schools open for in-class learning commencing on 18 January, 2022; however, all restaurants closed to all residents for in-person dining. Gyms and all entertainment venues closed to all residents. School buses comprise 45.95% of the heavy vehicle traffic.



Turning Movement Count Summary Report Including AM and PM Peak Hours All Vehicles Except Bicycles



Carss Street & Martin Street North Almonte, ON

Survey Date: Thursday, January 20, 2022 Start Time: 0700 AADT Factor: 1.0
 Weather AM: Clear -18° C Survey Duration: 6 Hrs. Survey Hours: 0700-1000 & 1500-1800
 Weather PM: Clear -22° C Surveyor(s): T. Carmody

Time Period	Carss St.				N/A				Martin St. (N)				Martin St. (N)				Street Total	Grand Total				
	Eastbound		Westbound		Northbound		Southbound		Northbound		Southbound		Northbound		Southbound							
	LT	ST	RT	UT	LT	ST	RT	UT	LT	ST	RT	UT	LT	ST	RT	UT			LT	ST	RT	UT
0700-0800	1	0	3	0	4	0	0	0	0	4	1	37	0	0	38	0	60	1	0	61	99	103
0800-0900	2	0	7	0	9	0	0	0	0	9	11	31	0	0	42	0	60	1	0	61	103	112
0900-1000	1	0	2	0	3	0	0	0	0	3	1	34	0	0	35	0	36	2	0	38	73	76
1500-1600	5	0	5	0	10	0	0	0	0	10	10	69	0	0	79	0	54	1	0	55	134	144
1600-1700	3	0	10	0	13	0	0	0	0	13	8	66	0	0	74	0	45	2	0	47	121	134
1700-1800	1	0	3	0	4	0	0	0	0	4	7	65	0	0	72	0	29	3	0	32	104	108
Totals	13	0	30	0	43	0	0	0	0	43	38	302	0	0	340	0	284	10	0	294	634	677

**Equivalent 12 & 24-Hour Vehicle Volumes Including the Annual Average Daily Traffic (AADT) Factor
Applicable to the Day and Month of the Turning Movement Count**

**Expansion factors are applied exclusively to standard weekday 8-hour turning movement counts
conducted during the hours of 0700h - 1000h, 1130h - 1330h and 1500h - 1800h**

Equivalent 12-hour vehicle volumes. These volumes are calculated by multiplying the 8-hour totals by the 8 → 12 expansion factor of 1.39																								
Equi. 12 Hr	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
Average daily 12-hour vehicle volumes. These volumes are calculated by multiplying the equivalent 12-hour totals by the AADT factor of: 1.0																								
AADT 12-hr	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
24-Hour AADT. These volumes are calculated by multiplying the average daily 12-hour vehicle volumes by the 12 → 24 expansion factor of 1.31																								
AADT 24 Hr	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a

AADT and expansion factors provided by the City of Ottawa

AM Peak Hour Factor → 0.77		Highest Hourly Vehicle Volume Between 0700h & 1000h																					
AM Peak Hr	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	Str. Tot.	Gr. Tot.	
0730-0830	2	0	8	0	10	0	0	0	0	0	10	7	39	0	0	46	0	77	2	0	79	125	135

PM Peak Hour Factor → 0.91		Highest Hourly Vehicle Volume Between 1500h & 1800h																					
PM Peak Hr	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	Str. Tot.	Gr. Tot.	
1515-1615	5	0	8	0	13	0	0	0	0	0	13	12	60	0	0	72	0	63	2	0	65	137	150

Comments:
 Traffic count was conducted during the SARS-CoV-2 (Covid-19) pandemic. All schools open for in-class learning commencing on 18 January, 2022; however, all restaurants closed to all residents for in-person dining. Gyms and all entertainment venues closed to all residents. School buses comprise 45.95% of the heavy vehicle traffic.



- Notes:**
- Includes all vehicle types except bicycles, electric bicycles, and electric scooters.
 - When expansion and AADT factors are applied, the results will differ slightly due to rounding.



Turning Movement Count Summary, AM and PM Peak Hour Flow Diagrams All Vehicles Except Bicycles



Carss Street & Ottawa Valley Rail Trail Almonte, ON






Turning Movement Count Heavy Vehicle Summary (FHWA Class 4-13) Flow Diagram



Carss Street & Ottawa Valley Rail Trail Almonte, ON



Time Period	Carss St. Eastbound				Carss St. Westbound				Ottawa Valley Rail Trail Northbound				Ottawa Valley Rail Trail Southbound			
	LT	ST	RT	UT	LT	ST	RT	UT	LT	ST	RT	UT	LT	ST	RT	UT
0700-0800	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
0800-0900	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
0900-1000	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1500-1600	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1600-1700	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1700-1800	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Totals	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0


Comments:
Traffic count conducted during the SARS-CoV-2 (Covid-19) pandemic. All schools open to in-person classes; however, all restaurants, gyms and entertainment venues open to vaccinated residents only. There were no heavy vehicles (school buses or trucks), bicycles or ATV's observed.



Turning Movement Count Pedestrian and Snowmobile Crossings Summary and Flow Diagram



Carss Street & Ottawa Valley Rail Trail Almonte, ON



Time Period	Ottawa Valley Rail Trail Crossing Carss St.	Street Total	South Side Crossing Ottawa Valley Rail Trail	North Side Crossing Ottawa Valley Rail Trail	Street Total	Grand Total
0700-0800	4	0	4	3	0	7
0800-0900	0	0	0	2	2	4
0900-1000	2	0	2	2	0	4
1500-1600	0	0	0	0	0	0
1600-1700	1	0	1	0	0	1
1700-1800	1	0	1	0	0	1
Totals	8	0	8	7	2	17

Comments:
Traffic count conducted during the SARS-CoV-2 (Covid-19) pandemic. All schools open to in-person classes; however, all restaurants, gyms and entertainment venues open to vaccinated residents only. There were no heavy vehicles (school buses or trucks), bicycles or ATV's observed.



Turning Movement Count Summary Report Including AM and PM Peak Hours All Vehicles Except Bicycles



Carss Street & Ottawa Valley Rail Trail Almonte, ON

Survey Date: Wednesday, February 16, 2022 Start Time: 0700 AADT Factor: 1.0
 Weather AM: Overcast -12° C Survey Duration: 6 Hrs. Survey Hours: 0700-1000 & 1500-1800
 Weather PM: Overcast +5° C Surveyor(s): T. Carmody

Time Period	Carss St. Eastbound				Carss St. Westbound				Ottawa Valley Rail Trail Northbound				Ottawa Valley Rail Trail Southbound				Grand Total			
	LT	ST	RT	UT	LT	ST	RT	UT	LT	ST	RT	UT	LT	ST	RT	UT				
	E/B Tot				W/B Tot				Street Total				S/B Tot							
0700-0800	0	1	0	0	1	0	1	0	0	1	2	0	0	0	0	0	0	0	0	2
0800-0900	0	3	0	0	3	0	1	0	0	1	4	0	0	0	0	0	0	0	0	4
0900-1000	0	3	0	0	3	0	2	0	0	2	5	0	0	0	0	0	0	0	0	5
1500-1600	0	7	0	0	7	0	7	0	0	7	14	0	0	0	0	0	0	0	0	14
1600-1700	0	3	0	0	3	0	4	0	0	4	7	0	0	0	0	0	0	0	0	7
1700-1800	0	2	0	0	2	0	4	0	0	4	6	0	0	0	0	0	0	0	0	6
Totals	0	19	0	0	19	0	19	0	0	19	38	0	0	0	0	0	0	0	0	38

**Equivalent 12 & 24-Hour Vehicle Volumes Including the Annual Average Daily Traffic (AADT) Factor
Applicable to the Day and Month of the Turning Movement Count**

Expansion factors are applied exclusively to standard weekday 8-hour turning movement counts conducted during the hours of 0700h - 1000h, 1130h - 1330h and 1500h - 1800h

Equivalent 12-hour vehicle volumes. These volumes are calculated by multiplying the 8-hour totals by the 8 → 12 expansion factor of 1.39																			
Equi. 12 Hr	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
Average daily 12-hour vehicle volumes. These volumes are calculated by multiplying the equivalent 12-hour totals by the AADT factor of: 1.0																			
AADT 12-hr	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
24-Hour AADT. These volumes are calculated by multiplying the average daily 12-hour vehicle volumes by the 12 → 24 expansion factor of 1.31																			
AADT 24 Hr	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a

AADT and expansion factors provided by the City of Ottawa

AM Peak Hour Factor → 0.50										Highest Hourly Vehicle Volume Between 0700h & 1000h									
AM Peak Hr	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	Str. Tot.	LT	ST	RT	UT	Total	Str. Tot.	Gr. Tot.	
0845-0945	0	4	0	0	4	0	2	0	0	2	6	0	0	0	0	0	0	0	6

PM Peak Hour Factor → 0.70										Highest Hourly Vehicle Volume Between 1500h & 1800h									
PM Peak Hr	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	Str. Tot.	LT	ST	RT	UT	Total	Str. Tot.	Gr. Tot.	
1515-1615	0	5	0	0	5	0	9	0	0	9	14	0	0	0	0	0	0	0	14

Comments:
 Traffic count conducted during the SARS-CoV-2 (Covid-19) pandemic. All schools open to in-person classes; however, all restaurants, gyms and entertainment venues open to vaccinated residents only. There were no heavy vehicles (school buses or trucks), bicycles or ATV's observed.

- Notes:**
- Includes all vehicle types except bicycles, electric bicycles, and electric scooters.
 - When expansion and AADT factors are applied, the results will differ slightly due to rounding.





Turning Movement Count Summary, AM and PM Peak Hour Flow Diagrams All Vehicles Except Bicycles



Carss Street & Union Street North Almonte, ON


All Vehicles
(Except Bicycles & Electric Scooters)

Wednesday, February 16, 2022
 0700-1000 & 1500-1800
 6 Hour Survey
 City of Ottawa Ward ► N/A





Turning Movement Count Heavy Vehicle Summary (FHWA Class 4 to 13) Flow Diagram




Time Period	Carss St.					Carss St.					Union St. (N)					N/A					
	Eastbound					Westbound					Northbound					Southbound					
	LT	ST	RT	UT	EB Tot	LT	ST	RT	UT	WB Tot	LT	ST	RT	UT	NB Tot	LT	ST	RT	UT	SB Tot	GR Tot
0700-0800	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
0800-0900	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
0900-1000	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1130-1230	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1230-1330	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1500-1600	0	0	0	0	0	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	1
1600-1700	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1700-1800	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Totals	0	0	0	0	0	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	1

Comments:
Traffic count conducted during the SARS-CoV-2 (Covid-19) pandemic. All schools open to in-person classes; however, all restaurants, gyms and entertainment venues open to vaccinated residents only. The single school bus comprised 100.00% of the heavy vehicle traffic. No bicycles were observed.



Turning Movement Count Pedestrian Crossings Summary and Flow Diagram



Time Period	West Side Crossing		Street Total	South Side Crossing		Street Total	North Side Crossing		Street Total	Grand Total
	Carss St.	Carss St.		Union St. (N)	N/A					
0700-0800	0	1	1	3		3		4		
0800-0900	1	0	1	3		3		4		
0900-1000	4	0	4	0		0		4		
1130-1230	0	0	0	0		0		0		
1230-1330	0	0	0	0		0		0		
1500-1600	0	1	1	2		2		3		
1600-1700	2	0	2	2		2		4		
1700-1800	0	2	2	2		2		4		
Totals	7	4	11	12		12		23		

Comments:
Traffic count conducted during the SARS-CoV-2 (Covid-19) pandemic. All schools open to in-person classes; however, all restaurants, gyms and entertainment venues open to vaccinated residents only. The single school bus comprised 100.00% of the heavy vehicle traffic. No bicycles were observed.



Turning Movement Count
Summary Report Including Peak Hours,
AADT and Expansion Factors
 All Vehicles Except Bicycles



Carss Street & Union Street North **Almonte, ON**

Survey Date: Wednesday, February 16, 2022 Start Time: 0700 AADT Factor: 1.0
 Weather AM: Overcast -12° C Survey Duration: 6 Hrs. Survey Hours: 0700-1000 & 1500-1800
 Weather PM: Overcast +5° C Surveyor(s): T. Carmody

Time Period	Carss St.					Carss St.					Union St. (N)					N/A							
	Eastbound					Westbound					Northbound					Southbound							
	LT	ST	RT	UT	E/B Tot	LT	ST	RT	UT	W/B Tot	Street Total	LT	ST	RT	UT	N/B Tot	LT	ST	RT	UT	S/B Tot	Street Total	Grand Total
0700-0800		1	0	0	1	0	1		0	1	2	0		1	0	1						1	3
0800-0900		2	1	0	3	1	1		0	2	5	0		1	0	1						1	6
0900-1000		2	1	0	3	1	2		0	3	6	0		1	0	1						1	7
1130-1230		0	0	0	0	0	0		0	0	0	0		0	0	0						0	0
1230-1330		0	0	0	0	0	0		0	0	0	0		0	0	0						0	0
1500-1600		5	2	0	7	1	4		1	6	13	3		2	0	5						5	18
1600-1700		3	0	0	3	0	3		0	3	6	1		1	0	2						2	8
1700-1800		0	2	0	2	2	3		0	5	7	1		2	0	3						3	10
Totals		13	6	0	19	5	14		1	20	39	5		8	0	13					13	52	

Equivalent 12 & 24-hour Vehicle Volumes Including the Annual Average Daily Traffic (AADT) Factor
Applicable to the Day and Month of the Turning Movement Count

Expansion factors are applied exclusively to standard weekday 8-hour turning movement counts conducted during the hours of 0700h - 1000h, 1130h - 1330h and 1500h - 1800h

Equivalent 12-hour vehicle volumes. These volumes are calculated by multiplying the 8-hour totals by the 8 → 12 expansion factor of 1.39

Equ. 12 Hr	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
------------	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----

Average daily 12-hour vehicle volumes. These volumes are calculated by multiplying the equivalent 12-hour totals by the AADT factor of: 1.0

AADT 12-hr	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
------------	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----

24-Hour AADT. These volumes are calculated by multiplying the average daily 12-hour vehicle volumes by the 12 → 24 expansion factor of 1.31

AADT 24 Hr	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
------------	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----

AADT and expansion factors provided by the City of Ottawa

AM Peak Hour Factor →	0.67					Highest Hourly Vehicle Volume Between 0700h & 1000h																								
AM Peak Hr	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	Str. Tot.	Gr. Tot.			
0845-0945	0	3	1	0	4	0	2	0	0	2	6	0	0	2	0	2	0	0	0	0	0	0	0	0	0	0	0	0	2	8
OFF Peak Hour Factor →	#DIV/0!					Highest Hourly Vehicle Volume Between 1130h & 1330h																								
OFF Peak Hr	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	Str. Tot.	Gr. Tot.			
1230-1330	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
PM Peak Hour Factor →	0.79					Highest Hourly Vehicle Volume Between 1500h & 1800h																								
PM Peak Hr	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	LT	ST	RT	UT	Total	Str. Tot.	Gr. Tot.			
1515-1615	0	3	2	0	5	1	5	0	1	7	12	4	0	3	0	7	0	0	0	0	0	0	0	0	0	0	0	0	7	19

Comments:
 Traffic count conducted during the SARS-CoV-2 (Covid-19) pandemic. All schools open to in-person classes; however, all restaurants, gyms and entertainment venues open to vaccinated residents only. The single school bus comprised 100.00% of the heavy vehicle traffic. No bicycles were observed.

- Notes:**
1. Includes all vehicle types except bicycles, electric bicycles, and electric scooters.
 2. When expansion and AADT factors are applied, the results will differ slightly due to rounding.

Appendix D

Heavy Vehicle Percentage Calculations

[1] Carss Street / Martin Street N												
AM												
	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
HV Volume	0	1	0	0	4	0	0	0	0	0	0	0
Total Volume	7	39	0	0	77	2	2	0	8	0	0	0
HV%	0%	3%	-	-	5%	0%	0%	-	0%	-	-	-
PM												
	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
HV Volume	1	3	0	0	5	0	3	0	1	0	0	0
Total Volume	12	60	0	0	63	2	5	0	8	0	0	0
HV%	8%	5%	-	-	8%	0%	60%	-	13%	-	-	-

[2] Carss Street / Union Street N												
AM												
	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
HV Volume	0	0	0	0	0	0	0	0	0	0	0	0
Total Volume	0	0	2	0	0	0	0	3	1	0	2	0
HV%	-	-	0%	-	-	-	-	0%	0%	-	0%	-
PM												
	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
HV Volume	0	0	0	0	0	0	0	0	0	1	0	0
Total Volume	4	0	3	0	0	0	0	3	2	2	5	0
HV%	0%	-	0%	-	-	-	-	0%	0%	50%	0%	-

Appendix E

2022 Existing Synchro Worksheets

Intersection						
Int Delay, s/veh	1.1					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Vol, veh/h	3	12	11	59	116	3
Future Vol, veh/h	3	12	11	59	116	3
Conflicting Peds, #/hr	0	1	0	0	0	1
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	77	77	77	77	77	77
Heavy Vehicles, %	2	2	2	3	5	2
Mvmt Flow	4	16	14	77	151	4

Major/Minor	Minor2	Major1	Major2			
Conflicting Flow All	259	155	156	0	-	0
Stage 1	154	-	-	-	-	-
Stage 2	105	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	730	891	1424	-	-	-
Stage 1	874	-	-	-	-	-
Stage 2	919	-	-	-	-	-
Platoon blocked, %				-	-	-
Mov Cap-1 Maneuver	721	889	1423	-	-	-
Mov Cap-2 Maneuver	721	-	-	-	-	-
Stage 1	864	-	-	-	-	-
Stage 2	918	-	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s	9.3	1.2	0
HCM LOS	A		

Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR
Capacity (veh/h)	1423	-	849	-	-
HCM Lane V/C Ratio	0.01	-	0.023	-	-
HCM Control Delay (s)	7.6	0	9.3	-	-
HCM Lane LOS	A	A	A	-	-
HCM 95th %tile Q(veh)	0	-	0.1	-	-

Intersection						
Int Delay, s/veh	1.6					
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Traffic Vol, veh/h	10	2	1	13	0	5
Future Vol, veh/h	10	2	1	13	0	5
Conflicting Peds, #/hr	0	0	0	0	2	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	67	67	67	67	67	67
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	15	3	1	19	0	7

Major/Minor	Major1	Major2	Minor1	Minor2	Minor3
Conflicting Flow All	0	0	18	0	40
Stage 1	-	-	-	-	17
Stage 2	-	-	-	-	23
Critical Hdwy	-	-	4.12	-	6.42
Critical Hdwy Stg 1	-	-	-	-	5.42
Critical Hdwy Stg 2	-	-	-	-	5.42
Follow-up Hdwy	-	-	2.218	-	3.518
Pot Cap-1 Maneuver	-	-	1599	-	972
Stage 1	-	-	-	-	1006
Stage 2	-	-	-	-	1000
Platoon blocked, %	-	-	-	-	-
Mov Cap-1 Maneuver	-	-	1599	-	969
Mov Cap-2 Maneuver	-	-	-	-	969
Stage 1	-	-	-	-	1006
Stage 2	-	-	-	-	997

Approach	EB	WB	NB
HCM Control Delay, s	0	0.5	8.4
HCM LOS			A

Minor Lane/Major Mvmt	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)	1062	-	-	1599	-
HCM Lane V/C Ratio	0.007	-	-	0.001	-
HCM Control Delay (s)	8.4	-	-	7.3	0
HCM Lane LOS	A	-	-	A	A
HCM 95th %tile Q(veh)	0	-	-	0	-

Intersection						
Int Delay, s/veh	1.5					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	T			T		
Traffic Vol, veh/h	8	12	18	90	95	3
Future Vol, veh/h	8	12	18	90	95	3
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	91	91	91	91	91	91
Heavy Vehicles, %	60	13	8	5	8	0
Mvmt Flow	9	13	20	99	104	3

Major/Minor	Minor2	Major1		Major2	
Conflicting Flow All	245	106	107	0	0
Stage 1	106	-	-	-	-
Stage 2	139	-	-	-	-
Critical Hdwy	7	6.33	4.18	-	-
Critical Hdwy Stg 1	6	-	-	-	-
Critical Hdwy Stg 2	6	-	-	-	-
Follow-up Hdwy	4.04	3.417	2.272	-	-
Pot Cap-1 Maneuver	633	919	1447	-	-
Stage 1	792	-	-	-	-
Stage 2	763	-	-	-	-
Platoon blocked, %				-	-
Mov Cap-1 Maneuver	624	919	1447	-	-
Mov Cap-2 Maneuver	624	-	-	-	-
Stage 1	780	-	-	-	-
Stage 2	763	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s	9.8	1.3	0
HCM LOS	A		

Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR
Capacity (veh/h)	1447	-	773	-	-
HCM Lane V/C Ratio	0.014	-	0.028	-	-
HCM Control Delay (s)	7.5	0	9.8	-	-
HCM Lane LOS	A	A	A	-	-
HCM 95th %tile Q(veh)	0	-	0.1	-	-

Intersection						
Int Delay, s/veh	3.5					
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Traffic Vol, veh/h	10	3	5	16	6	10
Future Vol, veh/h	10	3	5	16	6	10
Conflicting Peds, #/hr	0	2	2	0	1	1
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	79	79	79	79	79	79
Heavy Vehicles, %	2	2	50	2	2	2
Mvmt Flow	13	4	6	20	8	13

Major/Minor	Major1	Major2	Minor1	Minor2	Minor3
Conflicting Flow All	0	0	19	0	50
Stage 1	-	-	-	-	17
Stage 2	-	-	-	-	33
Critical Hdwy	-	-	4.6	-	6.42
Critical Hdwy Stg 1	-	-	-	-	5.42
Critical Hdwy Stg 2	-	-	-	-	5.42
Follow-up Hdwy	-	-	2.65	-	3.518
Pot Cap-1 Maneuver	-	-	1335	-	959
Stage 1	-	-	-	-	1006
Stage 2	-	-	-	-	989
Platoon blocked, %	-	-	-	-	-
Mov Cap-1 Maneuver	-	-	1333	-	951
Mov Cap-2 Maneuver	-	-	-	-	951
Stage 1	-	-	-	-	1004
Stage 2	-	-	-	-	983

Approach	EB	WB	NB
HCM Control Delay, s	0	1.8	8.6
HCM LOS			A

Minor Lane/Major Mvmt	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)	1015	-	-	1333	-
HCM Lane V/C Ratio	0.02	-	-	0.005	-
HCM Control Delay (s)	8.6	-	-	7.7	0
HCM Lane LOS	A	-	-	A	A
HCM 95th %tile Q(veh)	0.1	-	-	0	-

Appendix F

Signal Warrants

Carss St @ Martin St
 FB 2028

Justification #7

Justification	Description	Minimum Requirement		Minimum Requirement		Compliance			Signal
		1 Lane Highway		2 or More Lanes		Sectional		Entire %	
		Free Flow	Restr. Flow	Free Flow	Restr. Flow	Numerical	%		
1. Minimum Vehicular Volume	A. Vehicle volume, all approaches (average hour)	480	720	600	900	118	16%	8%	No
	B. Vehicle volume, along minor streets (average hour)	120	170	120	170	14	8%		
2. Delay to Cross Traffic	A. Vehicle volumes, major street (average hour)	480	720	600	900	108	15%	4%	No
	B. Combined vehicle and pedestrian volume crossing artery from minor streets (average hour)	50	75	50	75	3	4%		

Notes

1. Refer to OTM Book 12, pg 92, Mar 2012
2. Lowest section percentage governs justification
3. Average hourly volumes estimated from peak hour volumes, $AHV = PM/2$ or $(AM + PM) / 4$, including amplification factors
4. T-intersection factor corrected, applies only to 1B

Carss St @ Martin St
 FT 2028

Justification #7

Justification	Description	Minimum Requirement		Minimum Requirement		Compliance			Signal
		1 Lane Highway		2 or More Lanes		Sectional		Entire %	
		Free Flow	Restr. Flow	Free Flow	Restr. Flow	Numerical	%		
1. Minimum Vehicular Volume	A. Vehicle volume, all approaches (average hour)	480	720	600	900	147	20%	20%	No
	B. Vehicle volume, along minor streets (average hour)	120	170	120	170	38	22%		
2. Delay to Cross Traffic	A. Vehicle volumes, major street (average hour)	480	720	600	900	121	17%	10%	No
	B. Combined vehicle and pedestrian volume crossing artery from minor streets (average hour)	50	75	50	75	8	10%		

Notes

1. Refer to OTM Book 12, pg 92, Mar 2012
2. Lowest section percentage governs justification
3. Average hourly volumes estimated from peak hour volumes, $AHV = PM/2$ or $(AM + PM) / 4$, including amplification factors
4. T-intersection factor corrected, applies only to 1B

Carss St @ Union St
 FB 2028

Justification #7

Justification	Description	Minimum Requirement		Minimum Requirement		Compliance			Signal
		1 Lane Highway		2 or More Lanes		Sectional		Entire %	
		Free Flow	Restr. Flow	Free Flow	Restr. Flow	Numerical	%		
1. Minimum Vehicular Volume	A. Vehicle volume, all approaches (average hour)	480	720	600	900	22	3%	3%	No
	B. Vehicle volume, along minor streets (average hour)	120	170	120	170	9	5%		
2. Delay to Cross Traffic	A. Vehicle volumes, major street (average hour)	480	720	600	900	16	2%	2%	No
	B. Combined vehicle and pedestrian volume crossing artery from minor streets (average hour)	50	75	50	75	2	2%		

Notes

1. Refer to OTM Book 12, pg 92, Mar 2012
2. Lowest section percentage governs justification
3. Average hourly volumes estimated from peak hour volumes, $AHV = PM/2$ or $(AM + PM) / 4$, including amplification factors
4. T-intersection factor corrected, applies only to 1B

Future Access @ Carss St
 FB 2028

Justification #7

Justification	Description	Minimum Requirement		Minimum Requirement		Compliance		Signal	
		1 Lane Highway		2 or More Lanes		Sectional			Entire %
		Free Flow	Restr. Flow	Free Flow	Restr. Flow	Numerical	%		
1. Minimum Vehicular Volume	A. Vehicle volume, all approaches (average hour)	480	720	600	900	17	3%	0%	No
	B. Vehicle volume, along minor streets (average hour)	120	170	120	170	0	0%		
2. Delay to Cross Traffic	A. Vehicle volumes, major street (average hour)	480	720	600	900	17	3%	0%	No
	B. Combined vehicle and pedestrian volume crossing artery from minor streets (average hour)	50	75	50	75	0	0%		

Notes

1. Refer to OTM Book 12, pg 92, Mar 2012
2. Lowest section percentage governs justification
3. Average hourly volumes estimated from peak hour volumes, $AHV = PM/2$ or $(AM + PM) / 4$, including amplification factors
4. T-intersection factor corrected, applies only to 1B

Carss St @ Union St
 FT 2028

Justification #7

Justification	Description	Minimum Requirement		Minimum Requirement		Compliance			Signal
		1 Lane Highway		2 or More Lanes		Sectional		Entire %	
		Free Flow	Restr. Flow	Free Flow	Restr. Flow	Numerical	%		
1. Minimum Vehicular Volume	A. Vehicle volume, all approaches (average hour)	480	720	600	900	58	8%	8%	No
	B. Vehicle volume, along minor streets (average hour)	120	170	120	170	15	9%		
2. Delay to Cross Traffic	A. Vehicle volumes, major street (average hour)	480	720	600	900	49	7%	7%	No
	B. Combined vehicle and pedestrian volume crossing artery from minor streets (average hour)	50	75	50	75	6	8%		

Notes

1. Refer to OTM Book 12, pg 92, Mar 2012
2. Lowest section percentage governs justification
3. Average hourly volumes estimated from peak hour volumes, $AHV = PM/2$ or $(AM + PM) / 4$, including amplification factors
4. T-intersection factor corrected, applies only to 1B

Future Access @ Carss St
 FT 2028

Justification #7

Justification	Description	Minimum Requirement		Minimum Requirement		Compliance			Signal
		1 Lane Highway		2 or More Lanes		Sectional		Entire %	
		Free Flow	Restr. Flow	Free Flow	Restr. Flow	Numerical	%		
1. Minimum Vehicular Volume	A. Vehicle volume, all approaches (average hour)	480	720	600	900	53	11%	11%	No
	B. Vehicle volume, along minor streets (average hour)	120	170	120	170	29	24%		
2. Delay to Cross Traffic	A. Vehicle volumes, major street (average hour)	480	720	600	900	34	7%	7%	No
	B. Combined vehicle and pedestrian volume crossing artery from minor streets (average hour)	50	75	50	75	19	39%		

Notes

1. Refer to OTM Book 12, pg 92, Mar 2012
2. Lowest section percentage governs justification
3. Average hourly volumes estimated from peak hour volumes, $AHV = PM/2 \text{ or } (AM + PM) / 4$, including amplification factors
4. T-intersection factor corrected, applies only to 1B

Appendix G


Left-turn Lane Warrants

Carss Street at Martin Street 2028 FB

Design Speed Northbound Left

70 km/h

	EBL	EBT	EBR	WBL	WBT	WBR	Yes NBL	NBT	NBR	SBL	SBT	SBR	%Left Turn	Volume Advancing	Volume Opposing	
AM	3	0	13	0	0	0	0	12	65	0	0	127	3	15.6%	77	130
PM	9	0	13	0	0	0	0	20	98	0	0	104	3	16.9%	118	107





Carss Street at Martin Street 2028FT

Design Speed
80 km/h

Northbound Left


	EBL	EBT	EBR	WBL	WBT	WBR	Yes NBL	NBT	NBR	SBL	SBT	SBR	%Left Turn	Volume Advancing	Volume Opposing	
AM	10	0	43	0	0	0	0	26	65	0	0	127	6	28.6%	91	133
PM	20	0	28	0	0	0	0	52	98	0	0	104	7	34.7%	150	111






Carss Street at Union Street 2028 FB


Design Speed	Westbound Left	Yes											%Left Turn	Volume Advancing	Volume Opposing	
		EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT				SBR
80 km/h	AM	0	11	2	1	14	0	0	0	5	0	0	0	6.7%	15	13
	PM	0	11	3	5	17	0	7	0	11	0	0	0	22.7%	22	14






Carss Street at Union Street 2028 FT
 Design Speed Westbound Left
 60 km/h

	EBL	EBT	EBR	Yes WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR	%Left Turn	Volume Advancing	Volume Opposing
AM	0	48	9	1	31	0	0	0	5	0	0	0	3.1%	32	57
PM	0	37	10	5	53	0	23	0	11	0	0	0	8.6%	58	47





Appendix H

2028 Future Background Synchro Worksheets

Intersection						
Int Delay, s/veh	1.1					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Vol, veh/h	3	13	12	65	127	3
Future Vol, veh/h	3	13	12	65	127	3
Conflicting Peds, #/hr	0	1	0	0	0	1
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	77	77	77	77	77	77
Heavy Vehicles, %	2	2	2	3	5	2
Mvmt Flow	4	17	16	84	165	4

Major/Minor	Minor2	Major1	Major2			
Conflicting Flow All	284	169	170	0	-	0
Stage 1	168	-	-	-	-	-
Stage 2	116	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	706	875	1407	-	-	-
Stage 1	862	-	-	-	-	-
Stage 2	909	-	-	-	-	-
Platoon blocked, %				-	-	-
Mov Cap-1 Maneuver	696	873	1406	-	-	-
Mov Cap-2 Maneuver	696	-	-	-	-	-
Stage 1	851	-	-	-	-	-
Stage 2	908	-	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s	9.4	1.2	0
HCM LOS	A		

Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR
Capacity (veh/h)	1406	-	833	-	-
HCM Lane V/C Ratio	0.011	-	0.025	-	-
HCM Control Delay (s)	7.6	0	9.4	-	-
HCM Lane LOS	A	A	A	-	-
HCM 95th %tile Q(veh)	0	-	0.1	-	-

Intersection						
Int Delay, s/veh	1.5					
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Traffic Vol, veh/h	11	2	1	14	0	5
Future Vol, veh/h	11	2	1	14	0	5
Conflicting Peds, #/hr	0	0	0	0	2	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	67	67	67	67	67	67
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	16	3	1	21	0	7

Major/Minor	Major1	Major2	Minor1		
Conflicting Flow All	0	0	19	0	43
Stage 1	-	-	-	-	18
Stage 2	-	-	-	-	25
Critical Hdwy	-	-	4.12	-	6.42
Critical Hdwy Stg 1	-	-	-	-	5.42
Critical Hdwy Stg 2	-	-	-	-	5.42
Follow-up Hdwy	-	-	2.218	-	3.518
Pot Cap-1 Maneuver	-	-	1597	-	968
Stage 1	-	-	-	-	1005
Stage 2	-	-	-	-	998
Platoon blocked, %	-	-	-	-	-
Mov Cap-1 Maneuver	-	-	1597	-	965
Mov Cap-2 Maneuver	-	-	-	-	965
Stage 1	-	-	-	-	1005
Stage 2	-	-	-	-	995

Approach	EB	WB	NB
HCM Control Delay, s	0	0.5	8.4
HCM LOS			A

Minor Lane/Major Mvmt	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)	1061	-	-	1597	-
HCM Lane V/C Ratio	0.007	-	-	0.001	-
HCM Control Delay (s)	8.4	-	-	7.3	0
HCM Lane LOS	A	-	-	A	A
HCM 95th %tile Q(veh)	0	-	-	0	-

Intersection						
Int Delay, s/veh	1.5					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	T			T		T
Traffic Vol, veh/h	9	13	20	98	104	3
Future Vol, veh/h	9	13	20	98	104	3
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	91	91	91	91	91	91
Heavy Vehicles, %	60	13	8	5	8	0
Mvmt Flow	10	14	22	108	114	3

Major/Minor	Minor2	Major1		Major2	
Conflicting Flow All	268	116	117	0	0
Stage 1	116	-	-	-	-
Stage 2	152	-	-	-	-
Critical Hdwy	7	6.33	4.18	-	-
Critical Hdwy Stg 1	6	-	-	-	-
Critical Hdwy Stg 2	6	-	-	-	-
Follow-up Hdwy	4.04	3.417	2.272	-	-
Pot Cap-1 Maneuver	613	907	1435	-	-
Stage 1	783	-	-	-	-
Stage 2	752	-	-	-	-
Platoon blocked, %				-	-
Mov Cap-1 Maneuver	603	907	1435	-	-
Mov Cap-2 Maneuver	603	-	-	-	-
Stage 1	770	-	-	-	-
Stage 2	752	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s	9.9	1.3	0
HCM LOS	A		

Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR
Capacity (veh/h)	1435	-	752	-	-
HCM Lane V/C Ratio	0.015	-	0.032	-	-
HCM Control Delay (s)	7.5	0	9.9	-	-
HCM Lane LOS	A	A	A	-	-
HCM 95th %tile Q(veh)	0	-	0.1	-	-

Intersection						
Int Delay, s/veh	3.6					
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Traffic Vol, veh/h	11	3	5	17	7	11
Future Vol, veh/h	11	3	5	17	7	11
Conflicting Peds, #/hr	0	2	2	0	1	1
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	79	79	79	79	79	79
Heavy Vehicles, %	2	2	50	2	2	2
Mvmt Flow	14	4	6	22	9	14

Major/Minor	Major1	Major2	Minor1		
Conflicting Flow All	0	0	20	0	53 19
Stage 1	-	-	-	-	18 -
Stage 2	-	-	-	-	35 -
Critical Hdwy	-	-	4.6	-	6.42 6.22
Critical Hdwy Stg 1	-	-	-	-	5.42 -
Critical Hdwy Stg 2	-	-	-	-	5.42 -
Follow-up Hdwy	-	-	2.65	-	3.518 3.318
Pot Cap-1 Maneuver	-	-	1334	-	955 1059
Stage 1	-	-	-	-	1005 -
Stage 2	-	-	-	-	987 -
Platoon blocked, %	-	-	-	-	-
Mov Cap-1 Maneuver	-	-	1332	-	947 1056
Mov Cap-2 Maneuver	-	-	-	-	947 -
Stage 1	-	-	-	-	1003 -
Stage 2	-	-	-	-	981 -

Approach	EB	WB	NB
HCM Control Delay, s	0	1.8	8.6
HCM LOS			A

Minor Lane/Major Mvmt	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)	1011	-	-	1332	-
HCM Lane V/C Ratio	0.023	-	-	0.005	-
HCM Control Delay (s)	8.6	-	-	7.7	0
HCM Lane LOS	A	-	-	A	A
HCM 95th %tile Q(veh)	0.1	-	-	0	-

Appendix I

2028 Future Total Synchro Worksheets

Intersection						
Int Delay, s/veh	2.6					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Vol, veh/h	10	43	26	65	127	6
Future Vol, veh/h	10	43	26	65	127	6
Conflicting Peds, #/hr	0	1	0	0	0	1
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	77	77	77	77	77	77
Heavy Vehicles, %	2	2	2	3	5	2
Mvmt Flow	13	56	34	84	165	8

Major/Minor	Minor2	Major1	Major2			
Conflicting Flow All	322	171	174	0	-	0
Stage 1	170	-	-	-	-	-
Stage 2	152	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	672	873	1403	-	-	-
Stage 1	860	-	-	-	-	-
Stage 2	876	-	-	-	-	-
Platoon blocked, %				-	-	-
Mov Cap-1 Maneuver	654	871	1402	-	-	-
Mov Cap-2 Maneuver	654	-	-	-	-	-
Stage 1	838	-	-	-	-	-
Stage 2	875	-	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s	9.8	2.2	0
HCM LOS	A		

Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR
Capacity (veh/h)	1402	-	820	-	-
HCM Lane V/C Ratio	0.024	-	0.084	-	-
HCM Control Delay (s)	7.6	0	9.8	-	-
HCM Lane LOS	A	A	A	-	-
HCM 95th %tile Q(veh)	0.1	-	0.3	-	-

Intersection						
Int Delay, s/veh	0.5					
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Traffic Vol, veh/h	48	9	1	31	0	5
Future Vol, veh/h	48	9	1	31	0	5
Conflicting Peds, #/hr	0	0	0	0	2	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	67	67	67	67	67	67
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	72	13	1	46	0	7

Major/Minor	Major1	Major2	Minor1	Minor2	Minor3
Conflicting Flow All	0	0	85	0	129
Stage 1	-	-	-	-	79
Stage 2	-	-	-	-	50
Critical Hdwy	-	-	4.12	-	6.42
Critical Hdwy Stg 1	-	-	-	-	5.42
Critical Hdwy Stg 2	-	-	-	-	5.42
Follow-up Hdwy	-	-	2.218	-	3.518
Pot Cap-1 Maneuver	-	-	1512	-	865
Stage 1	-	-	-	-	944
Stage 2	-	-	-	-	972
Platoon blocked, %	-	-	-	-	-
Mov Cap-1 Maneuver	-	-	1512	-	862
Mov Cap-2 Maneuver	-	-	-	-	862
Stage 1	-	-	-	-	944
Stage 2	-	-	-	-	969

Approach	EB	WB	NB
HCM Control Delay, s	0	0.2	8.7
HCM LOS			A

Minor Lane/Major Mvmt	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)	981	-	-	1512	-
HCM Lane V/C Ratio	0.008	-	-	0.001	-
HCM Control Delay (s)	8.7	-	-	7.4	0
HCM Lane LOS	A	-	-	A	A
HCM 95th %tile Q(veh)	0	-	-	0	-

Intersection						
Int Delay, s/veh	4.6					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		↕	↕		↕	
Traffic Vol, veh/h	0	13	14	17	44	0
Future Vol, veh/h	0	13	14	17	44	0
Conflicting Peds, #/hr	5	0	0	5	5	5
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	67	67	67	67	67	67
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	0	19	21	25	66	0

Major/Minor	Major1	Major2	Minor2		
Conflicting Flow All	51	0	-	0	63 44
Stage 1	-	-	-	-	39 -
Stage 2	-	-	-	-	24 -
Critical Hdwy	4.12	-	-	-	6.42 6.22
Critical Hdwy Stg 1	-	-	-	-	5.42 -
Critical Hdwy Stg 2	-	-	-	-	5.42 -
Follow-up Hdwy	2.218	-	-	-	3.518 3.318
Pot Cap-1 Maneuver	1555	-	-	-	943 1026
Stage 1	-	-	-	-	983 -
Stage 2	-	-	-	-	999 -
Platoon blocked, %		-	-	-	
Mov Cap-1 Maneuver	1548	-	-	-	934 1016
Mov Cap-2 Maneuver	-	-	-	-	934 -
Stage 1	-	-	-	-	978 -
Stage 2	-	-	-	-	994 -

Approach	EB	WB	SB
HCM Control Delay, s	0	0	9.1
HCM LOS			A

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)	1548	-	-	-	934
HCM Lane V/C Ratio	-	-	-	-	0.07
HCM Control Delay (s)	0	-	-	-	9.1
HCM Lane LOS	A	-	-	-	A
HCM 95th %tile Q(veh)	0	-	-	-	0.2

Intersection						
Int Delay, s/veh	2.9					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	T		T		T	
Traffic Vol, veh/h	20	28	52	98	104	7
Future Vol, veh/h	20	28	52	98	104	7
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	91	91	91	91	91	91
Heavy Vehicles, %	60	13	8	5	8	0
Mvmt Flow	22	31	57	108	114	8

Major/Minor	Minor2	Major1		Major2	
Conflicting Flow All	340	118	122	0	0
Stage 1	118	-	-	-	-
Stage 2	222	-	-	-	-
Critical Hdwy	7	6.33	4.18	-	-
Critical Hdwy Stg 1	6	-	-	-	-
Critical Hdwy Stg 2	6	-	-	-	-
Follow-up Hdwy	4.04	3.417	2.272	-	-
Pot Cap-1 Maneuver	553	905	1429	-	-
Stage 1	782	-	-	-	-
Stage 2	695	-	-	-	-
Platoon blocked, %				-	-
Mov Cap-1 Maneuver	530	905	1429	-	-
Mov Cap-2 Maneuver	530	-	-	-	-
Stage 1	749	-	-	-	-
Stage 2	695	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s	10.6	2.6	0
HCM LOS	B		

Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR
Capacity (veh/h)	1429	-	699	-	-
HCM Lane V/C Ratio	0.04	-	0.075	-	-
HCM Control Delay (s)	7.6	0	10.6	-	-
HCM Lane LOS	A	A	B	-	-
HCM 95th %tile Q(veh)	0.1	-	0.2	-	-

Intersection						
Int Delay, s/veh	2.5					
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Traffic Vol, veh/h	37	10	5	53	23	11
Future Vol, veh/h	37	10	5	53	23	11
Conflicting Peds, #/hr	0	2	2	0	1	1
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	79	79	79	79	79	79
Heavy Vehicles, %	2	2	50	2	2	2
Mvmt Flow	47	13	6	67	29	14

Major/Minor	Major1	Major2	Minor1		
Conflicting Flow All	0	0	62	0	136 57
Stage 1	-	-	-	-	56 -
Stage 2	-	-	-	-	80 -
Critical Hdwy	-	-	4.6	-	6.42 6.22
Critical Hdwy Stg 1	-	-	-	-	5.42 -
Critical Hdwy Stg 2	-	-	-	-	5.42 -
Follow-up Hdwy	-	-	2.65	-	3.518 3.318
Pot Cap-1 Maneuver	-	-	1284	-	857 1009
Stage 1	-	-	-	-	967 -
Stage 2	-	-	-	-	943 -
Platoon blocked, %	-	-	-	-	-
Mov Cap-1 Maneuver	-	-	1282	-	850 1006
Mov Cap-2 Maneuver	-	-	-	-	850 -
Stage 1	-	-	-	-	965 -
Stage 2	-	-	-	-	937 -

Approach	EB	WB	NB
HCM Control Delay, s	0	0.7	9.2
HCM LOS			A

Minor Lane/Major Mvmt	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)	895	-	-	1282	-
HCM Lane V/C Ratio	0.048	-	-	0.005	-
HCM Control Delay (s)	9.2	-	-	7.8	0
HCM Lane LOS	A	-	-	A	A
HCM 95th %tile Q(veh)	0.2	-	-	0	-

Intersection						
Int Delay, s/veh	2.4					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		↕	↕		↕	
Traffic Vol, veh/h	0	14	26	52	33	0
Future Vol, veh/h	0	14	26	52	33	0
Conflicting Peds, #/hr	5	0	0	5	5	5
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	79	79	79	79	79	79
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	0	18	33	66	42	0

Major/Minor	Major1	Major2	Minor2		
Conflicting Flow All	104	0	-	0	94 76
Stage 1	-	-	-	-	71 -
Stage 2	-	-	-	-	23 -
Critical Hdwy	4.12	-	-	-	6.42 6.22
Critical Hdwy Stg 1	-	-	-	-	5.42 -
Critical Hdwy Stg 2	-	-	-	-	5.42 -
Follow-up Hdwy	2.218	-	-	-	3.518 3.318
Pot Cap-1 Maneuver	1488	-	-	-	906 985
Stage 1	-	-	-	-	952 -
Stage 2	-	-	-	-	1000 -
Platoon blocked, %		-	-	-	
Mov Cap-1 Maneuver	1481	-	-	-	897 976
Mov Cap-2 Maneuver	-	-	-	-	897 -
Stage 1	-	-	-	-	947 -
Stage 2	-	-	-	-	995 -

Approach	EB	WB	SB
HCM Control Delay, s	0	0	9.2
HCM LOS			A

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)	1481	-	-	-	897
HCM Lane V/C Ratio	-	-	-	-	0.047
HCM Control Delay (s)	0	-	-	-	9.2
HCM Lane LOS	A	-	-	-	A
HCM 95th %tile Q(veh)	0	-	-	-	0.1